

# Work Write-Up and Bid Document/By Trade

**Rosella Owens**

Contractor Name:

11815 N. 190th E. Ave. Collinsville, OK 7-  
(918) 837-0617

Contractor Signature:

This document must be signed to be a valid bid.

PROJECT TYPE: **Rehabilitation**

Bid Due Date:

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
<b>Appliances</b>				
1	Area: KITCHEN Dishwasher/Install new. Install new Energy Star certified dishwasher. Install new dishwasher	Div.# 10.F.	1 Ea	<input type="text"/>
2	Area: KITCHEN Dryer Vent/Replace. Replace existing dryer vent with new louvered dryer vent and ducting. Install new dryer vent	Div.# 10.D. 2.D.	1 Ea	<input type="text"/>
3	Area: KITCHEN Oven/Range/Gas/30"/Free Standing. Install new 30" free standing gas range/oven with dock, oven window and one-year manufacturer's warranty. Install new Range	Div.# 10.F.	1 Ea	<input type="text"/>
4	Area: KITCHEN Refrigerator/Top Freezer/Energy Star/18.2 C.F. Minimum Size/Install new. Install new 18.2 C.F. (minimum size) refrigerator with top freezer. Must be Energy Star compliant. Install new Refrigerator	Div.# 10.F.	1 Ea	<input type="text"/>

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<b>Appliances</b>				
5	<i>Area: KITCHEN</i> Vent-A-Hood/30"/Recirc./Install new kitchen vent-a-hood (recirc.)/30" Install new Venthood	Div.# 10.D. 3.D	1 Ea	<input type="text"/>
<b>Carpentry</b>				
6	<i>Area: KITCHEN</i> Base Cabinets/Install/Oak. Install new base cabinets/pre-finished oak. Install new base cabinets	Div.# 6.O.2	10 LF	<input type="text"/>
7	<i>Area: INTERIOR</i> Base Trim/Pine Colonial 2-1/4" Fingerjoint/Replace. Replace base trim, colonial, fingerjoint, 2-1/4" pine. Replace all trim. Paint all trim white	Div.# 6.N	650 LF	<input type="text"/>
8	<i>Area: LIVING ROOM #1</i> Closet Shelf & Clothes Rod/Wood. Install new wood closet shelf (1" x 12") and clothes rod. Work shall include bracing and paint (prime and two coats). Install new closet rod	Div.# 6.Z.	6 LF	<input type="text"/>
9	<i>Area: BEDROOM #1</i> Clothes Rod/Install. Install new closet clothes rod. Install new closet rod	Div.# 6.Z.	5 LF	<input type="text"/>
10	<i>Area: BEDROOM #2</i> Clothes Rod/Install. Install new closet clothes rod. Install new Closet Rod	Div.# 6.Z.	4 LF	<input type="text"/>

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<b>Carpentry</b>				
11	<i>Area: BATHROOM #1</i> Countertop/New/Post Form Top. Install new countertop and backsplash. <i>Install new Countertop</i>	Div.# 6.0.4.	3 LF	<input type="text"/>
12	<i>Area: KITCHEN</i> Countertop/New/Post Form Top. Install new countertop and backsplash. <i>Install new countertops</i>	Div.# 6.0.4.	11 LF	<input type="text"/>
13	<i>Area: EXTERIOR</i> Door/Exterior/6-Panel Steel/Pre-Hung/Install. Install new exterior entrance door, pre-hung-steel six panel. Work shall include paint-both sides, lockset, deadbolt & peephole. <i>Install all new exterior doors</i>	Div.# 8.A.	4 Ea	<input type="text"/>
14	<i>Area: INTERIOR</i> Equipment Closet/Frame Equipment Platform for new equipment installation. Sheet rock tape, texture, inside and outside of closet. Install a door, and knob. Paint two coats. <i>Rebuild equipment closet for HWT and HVAC. Complete w/platform</i>	Div.# 2.A	120 SF	<input type="text"/>
15	<i>Area: EXTERIOR</i> Exterior Wall/Replace. Replace 2" x 4" x 8' exterior wall/ 16" O.C. (framing only). <i>Install new exterior wall</i>	Div.# 6.C.	10 LF	<input type="text"/>
16	<i>Area: EXTERIOR</i> Interior Wall/Loadbearing/2"x4"x10'/Replace. Replace 2" x 4" x 10' interior loadbearing wall/ 16" O.C. (framing only). <i>Reframe exterior wall to spec</i>	Div.# 6.C.	12 LF	<input type="text"/>

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<b>Carpentry</b>				
<b>17 Area: INTERIOR</b>				
	Interior Wall/Remove. Remove interior wall. Repair to adjacent surfaces to be addressed in a separate repair item.	Div.# 6	8 SF	<input type="text"/>
	<b>Remove wall between kitchen and living room</b>			
<b>18 Area: BATHROOM #1</b>				
	Mirror/Beveled Glass/Replace. Replace mirror with new beveled glass mirror. Repair all surfaces to match existing.	Div.# 10.E.	4 SF	<input type="text"/>
	<b>Install new Vanity Mirror</b>			
<b>19 Area: BATHROOM #1</b>				
	Paper Holder/Replace paper holder	Div.# 10.E.	1 Ea	<input type="text"/>
	<b>Install new Paper Holder</b>	2.		
<b>20 Area: BEDROOM #1</b>				
	Passage Door/Pre-Hung/6-Panel. Install new passage door & lockset (pre-hung 6-Panel). Work shall include paint both sides.	Div.# 8.A	1 Ea	<input type="text"/>
	<b>Remove &amp; Replace Closet Door. Match size and swing. Paint both sides of Door White</b>			
<b>21 Area: BEDROOM #1</b>				
	Passage Door/Pre-Hung/6-Panel. Install new passage door & lockset (pre-hung 6-Panel). Work shall include paint both sides.	Div.# 8.A	1 Ea	<input type="text"/>
	<b>Remove &amp; Replace BR entry door. Match existing size and swing. Paint both sides of Door</b>			

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<b>Carpentry</b>				
<b>22</b>	<i>Area: BEDROOM #2</i> Passage Door/Pre-Hung/6-Panel. Install new passage door & lockset (pre-hung 6-Panel). Work shall include paint both sides. <b>Remove &amp; Replace Br entry door. Match size and swing. Paint both sides of door White</b>	<i>Div.# 8.A</i>	1 Ea	<input type="text"/>
<b>23</b>	<i>Area: BEDROOM #2</i> Passage Door/Pre-Hung/6-Panel. Install new passage door & lockset (pre-hung 6-Panel). Work shall include paint both sides. <b>Remove &amp; Replace Closet Door. Match size and swing. Paint both sides of door White</b>	<i>Div.# 8.A</i>	1 Ea	<input type="text"/>
<b>24</b>	<i>Area: LIVING ROOM #1</i> Passage Door/Pre-Hung/6-Panel. Install new passage door & lockset (pre-hung 6-Panel). Work shall include paint both sides. <b>Install new closet door</b>	<i>Div.# 8.A</i>	1 Ea	<input type="text"/>
<b>25</b>	<i>Area: EXTERIOR</i> Post/Porch/4" x 4" Pressure Treated/Replace. Replace 4" x 4" support post with metal standoff post base. <b>Install new porch posts</b>	<i>Div.# 6.KK.</i>	32 LF	<input type="text"/>
<b>26</b>	<i>Area: INTERIOR</i> Replace damaged siding with new siding. Match existing. Prep and finish to match existing. <b>Install siding on exterior walls. Pressure wash all Vinyl siding.</b>	<i>Div.# 15.</i>	400 Ea	<input type="text"/>

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<b>Carpentry</b>				
<b>27 Area: EXTERIOR</b>				
	Room Addition/Wall Framing System. Install complete wall framing system including studs, top & bottom plates, bracing, insulation, sheathing, tyvek-type house wrap and drywall (fully finished).	Div.# 6.DD.	400 SF	<input type="text"/>
	Rebuild storage room and exterior walls to original design. Frame for 3' doors & twin window.			
<b>28 Area: EXTERIOR</b>				
	Storm Door/Vinyl Clad/Install. Install new self storing storm door, vinyl clad. Use Larson model 298-SS or written approved equal.	Div.# 8.B	3 Ea	<input type="text"/>
	Install new Storm Doors			
<b>29 Area: BATHROOM #1</b>				
	Towel Bar/Replace. Replace existing towel bar with new towel bar. Match existing size or as specified in Comments below.	Div.# 10.E. 2.	2 Ea	<input type="text"/>
	Install new Towel Bars			
<b>30 Area: BATHROOM #1</b>				
	Vanity Base Cabinet/Pre-Finished Oak. Install new vanity base cabinet (pre-finished oak).	Div.# 6.O	3 LF	<input type="text"/>
	Install new Vanity Cabinet			
<b>31 Area: KITCHEN</b>				
	Wall Hung Cabinets/Pre-Finished Oak. Install new wall hung cabinets (pre-finished oak).	Div.# 6.O.2	10 LF	<input type="text"/>
	Install new upper cabinets			
<b>32 Area: INTERIOR</b>				
	Wall/Partition/Demolish. Completely remove partition wall.	Div.# 9.D.1.	30 LF	<input type="text"/>
	Remove carport enclosure, walls on west, east and north side of home			

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<b>Carpentry</b>				
<b>33</b>	<i>Area: BEDROOM #1</i> Window Stool/Replace window stool (interior). Replace both window stools and paint White.	Div.# 8.R	6 LF	<input type="text"/>
<b>34</b>	<i>Area: BEDROOM #2</i> Window Stool/Replace window stool (interior). Remove & Replace Window Stools	Div.# 8.R	6 LF	<input type="text"/>
<b>35</b>	<i>Area: KITCHEN</i> Window Stool/Replace window stool (interior). Replace window stool	Div.# 8.R	3 LF	<input type="text"/>
<b>36</b>	<i>Area: LIVING ROOM #1</i> Window Stool/Replace window stool (interior). Remove and Replace window stool	Div.# 8.R	6 LF	<input type="text"/>
<b>37</b>	<i>Area: BEDROOM #1</i> Window/Replace/Vinyl/Thermopane/Low-E. Replace window with new Solid Vinyl window/single hung. Use Am. Craftsman Series 2160-Vinyl or written approved equal. Include frame, sill, sash, trim, hardware, screen, repair & paint of int. and ext. surfaces. Replace both windows.	Div.# 8.G	2 Ea	<input type="text"/>
<b>38</b>	<i>Area: BEDROOM #2</i> Window/Replace/Vinyl/Thermopane/Low-E. Replace window with new Solid Vinyl window/single hung. Use Am. Craftsman Series 2160-Vinyl or written approved equal. Include frame, sill, sash, trim, hardware, screen, repair & paint of int. and ext. surfaces. Remove & Replace Windows	Div.# 8.G	2 Ea	<input type="text"/>

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<b>Carpentry</b>				
<b>39</b>	<i>Area:</i> <b>KITCHEN</b>			
	Window/Replace/Vinyl/Thermopanel/Low-E. Replace window with new Solid Vinyl window/single hung. Use Am. Craftsman Series 2160-Vinyl or written approved equal. Include frame, sill, sash, trim, hardware, screen, repair & paint of int. and ext. surfaces. <b>Install new window. Match existing size</b>	<i>Div.#</i> 8.G	1 Ea	<input type="text"/>
<b>40</b>	<i>Area:</i> <b>LIVING ROOM #1</b>			
	Window/Replace/Vinyl/Thermopanel/Low-E. Replace window with new Solid Vinyl window/single hung. Use Am. Craftsman Series 2160-Vinyl or written approved equal. Include frame, sill, sash, trim, hardware, screen, repair & paint of int. and ext. surfaces. <b>Install new windows</b>	<i>Div.#</i> 8.G	2 Ea	<input type="text"/>
<b>Drywall &amp; Finish</b>				
<b>41</b>	<i>Area:</i> <b>GARAGE</b>			
	Drywall/Wall/Replace 5/8" drywall on wall/Finish completely. Work shall include tape, bed and texture to match existing surfaces. <b>Remove attic access, ceiling fan, and vent on carport &amp; install sheetrock. Tape &amp; texture to match.</b>	<i>Div.#</i> 9.D	12 SF	<input type="text"/>
<b>Electrical</b>				
<b>42</b>	<i>Area:</i> <b>BEDROOM #1</b>			
	Ceiling Fan, Light Kit & Circuit Wiring/52". Install new ceiling fan (52" w/lifetime warranty) with light kit, switch, cover plate and wiring. <b>Install new ceiling fan.</b>	<i>Div.#</i> 13.D. 9.B	1 Ea	<input type="text"/>



<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<b>Electrical</b>				
<b>43</b>	<i>Area: BEDROOM #2</i> Ceiling Fan, Light Kit & Circuit Wiring/52". Install new ceiling fan (52" w/lifetime warranty) with light kit, switch, cover plate and wiring. <i>Install new ceiling fan.</i>	<i>Div.# 13.D. 9.B</i>	1 Ea	<input type="text"/>
<b>44</b>	<i>Area: LIVING ROOM #1</i> Ceiling Fan, Light Kit & Circuit Wiring/52". Install new ceiling fan (52" w/lifetime warranty) with light kit, switch, cover plate and wiring. <i>Install new ceiling fan</i>	<i>Div.# 13.D. 9.B</i>	1 Ea	<input type="text"/>
<b>45</b>	<i>Area: LIVING ROOM #1</i> Door Bell System/Install new door bell system with bell chime, transformer, one button and bellwire. <i>Install new door bell</i>	<i>Div.# 13.D.</i>	1 Ea	<input type="text"/>
<b>46</b>	<i>Area: KITCHEN</i> Dryer Outlet/220v. Replace 220 dryer outlet & cover. <i>Install new dryer outlet</i>	<i>Div.# 13.D.</i>	1 Ea	<input type="text"/>
<b>47</b>	<i>Area: BATHROOM #1</i> Light Fixture/Heat-Vent-Light/Install new bathroom light (100 watt), heater (1450 watt), vent fan (70 CFM) and switch. Fan shall be vented out of attic to code. <i>Install new Heat-Vent-Light</i>	<i>Div.# 13.D. 16</i>	1 Ea	<input type="text"/>

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<b>Electrical</b>				
<b>48</b>	<i>Area: EXTERIOR</i> Light Fixture/Porch/Wall Mounted/Install new exterior porch light and circuit wiring. <i>Install new exterior light</i>	<i>Div.# 13.D. 9</i>	3 Ea	<input type="text"/>
<b>49</b>	<i>Area: KITCHEN</i> Light Fixture/Room/Replace. Replace existing light fixture with new 15 inch, round, flush mount, ceiling light fixture and 55 watt compact flourescant lighting. Fixture allowance \$55.00. <i>Install new light</i>	<i>Div.# 13.D. 9</i>	1 Ea	<input type="text"/>
<b>50</b>	<i>Area: BATHROOM #1</i> Outlet/110v Duplex/20 Amp/Grounded/Replace 110 duplex outlet and cover/20 amp., grounded. <i>Replace outlet and cover plate</i>	<i>Div.# 13.D.</i>	1 Ea	<input type="text"/>
<b>51</b>	<i>Area: BEDROOM #1</i> Outlet/110v Duplex/20 Amp/Grounded/Replace 110 duplex outlet and cover/20 amp., grounded. <i>Replace all outlets and covers</i>	<i>Div.# 13.D.</i>	5 Ea	<input type="text"/>
<b>52</b>	<i>Area: BEDROOM #2</i> Outlet/110v Duplex/20 Amp/Grounded/Replace 110 duplex outlet and cover/20 amp., grounded. <i>Install new outlets and cover plates</i>	<i>Div.# 13.D.</i>	5 Ea	<input type="text"/>

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<b>Electrical</b>				
<b>53 Area: KITCHEN</b>				
	Outlet/110v Duplex/20 Amp/Grounded/Replace 110 duplex outlet and cover/20 amp., grounded.	Div.# 13.D.	3 Ea	<input type="text"/>
	<b>Install new outlets</b>			
<b>54 Area: LIVING ROOM #1</b>				
	Outlet/110v Duplex/20 Amp/Grounded/Replace 110 duplex outlet and cover/20 amp., grounded.	Div.# 13.D.	5 Ea	<input type="text"/>
	<b>Install new outlets and covers</b>			
<b>55 Area: ATTIC</b>				
	Rewire Elect. System/Entire House. Replace all wiring, outlets, switches, fixtures and devices, bath heat/vent/light combo, hardwired smoke detectors, GFCI, ARC Fault, to new NEC location requirements. Panel Box shall be bid as separate item.	Div.# 13.D. 22	1400 SF	<input type="text"/>
	<b>Repair all wiring to design and code</b>			
<b>56 Area: BEDROOM #1</b>				
	Smoke Detector/Battery Operated/Install new smoke detector, battery operated (10 year lithium battery). All bedrooms and hallways adjacent to bedrooms. Use Firex #4015 or written approved equal.	Div.# 13.D. 11	1 Ea	<input type="text"/>
	<b>Install new smoke alarm</b>			
<b>57 Area: BEDROOM #2</b>				
	Smoke Detector/Battery Operated/Install new smoke detector, battery operated (10 year lithium battery). All bedrooms and hallways adjacent to bedrooms. Use Firex #4015 or written approved equal.	Div.# 13.D. 11	1 Ea	<input type="text"/>
	<b>Install new smoke alarm</b>			

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
<b>Electrical</b>				
<b>58</b> Area: <b>BEDROOM #1</b>	Switch & Cover Plate/20 Amp/Replace switch and cover/20 amp. Replace switch and cover plate	Div.# 13.D.	1 Ea	<input type="text"/>
<b>59</b> Area: <b>BEDROOM #2</b>	Switch & Cover Plate/20 Amp/Replace switch and cover/20 amp. Install new switch and cover plate	Div.# 13.D.	2 Ea	<input type="text"/>
<b>60</b> Area: <b>KITCHEN</b>	Switch & Cover Plate/20 Amp/Replace switch and cover/20 amp. Install new light switch	Div.# 13.D.	1 Ea	<input type="text"/>
<b>61</b> Area: <b>LIVING ROOM #1</b>	Switch & Cover Plate/20 Amp/Replace switch and cover/20 amp. Install new light switches	Div.# 13.D.	6 Ea	<input type="text"/>
<b>Flooring</b>				
<b>62</b> Area: <b>INTERIOR</b>	Vinyl Floor Tile. Replace existing flooring with new vinyl floor tile/12" x 12" x 1/8". Install all new Vinyl Plank flooring	Div.# 9.L	1200 SF	<input type="text"/>
<b>HVAC</b>				
<b>63</b> Area: <b>KITCHEN</b>	HVAC Equipment/Central/Cooling & Gas Heating/3 TON/14 SEER/New. Install new HVAC cooling equipment (14 SEER). INSIDE AND OUTSIDE EQUIPMENT/INCLUDING AIR HANDLER, COPPER LINES, CONDENSOR COILS, EVAP. COILS. Thermostat AND COMPRESSOR. Install new HVAC System	Div.# 12	1 Ea	<input type="text"/>

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<b>Paint &amp; Finish</b>				
<b>64</b>	<i>Area: INTERIOR</i> Walls & Ceiling/Drywall/Paint/Two coats. Paint walls & ceiling in entire area. Work shall include minor repairs to surfaces. SF=ACTUAL SURFACE AREA OF WALLS & CEILING. <b>Paint entire Interior of home white including closets two coats</b>	<i>Div.# 9.N.3</i>	1700 SF	<input type="text"/>
<b>Plumbing</b>				
<b>65</b>	<i>Area: BATHROOM #1</i> Commode/High Rise/Replace existing commode with new high rise commode with two (2) grab bars. Work shall include new shutoff, supply line and wax ring. Examine condition of the flange and report if damaged. Consult owner for location of grab bars. <b>Install new High Rise Toilet</b>	<i>Div.# 16.C.</i>	1 Ea	<input type="text"/>
<b>66</b>	<i>Area: EXTERIOR</i> Gas Lines/Cap/Entire Structure. Cap all gas lines in and under structure. All gas lines not connected to code-approved appliances and heating sources. <b>Cap all plumbing supply &amp; drain lines located on carport where utility room was removed</b>	<i>Div.# 11.A</i>	1 Ea	<input type="text"/>
<b>67</b>	<i>Area: EXTERIOR</i> Hose bib. Replace exterior hose bib with new brass hose bib with vacuum breaker. <b>Intall new hose bib</b>	<i>Div.# 11.A</i>	2 Ea	<input type="text"/>
<b>68</b>	<i>Area: BATHROOM #1</i> Shower Faucet & Diverter/Single Lever/Install new bath/shower faucet with diverter. Work shall include installation of pre-fab access panel or removal and replacement of wall materials on opposite wall to faucet. <b>Install new Shower Valve, Diverter, &amp; Shower Head</b>	<i>Div.# 11.A</i>	1 Ea	<input type="text"/>

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<b>Plumbing</b>				
<b>69</b>	<i>Area: BATHROOM #1</i> Sink & Faucet//Install new vanity sink & faucet, supply lines & shutoffs, all related plumbing. Delta. <b>Replace Vanity sink and faucet</b>	<i>Div.# 11.A</i>	1 Ea	<input type="text"/>
<b>70</b>	<i>Area: KITCHEN</i> Sink & Faucet/Kitchen. Install new stainless stell kitchen sink (33" x 22" x 7") & Faucet (Use Delta single-handle model100-WF or written approved equal). Work shall include new drain lines, trap and shutoffs (2). <b>Install new sink &amp; faucet w/sprayer</b>	<i>Div.# 11.A</i>	1 Ea	<input type="text"/>
<b>71</b>	<i>Area: KITCHEN</i> Washer Box, Valves & Drain/Replace. Replace existing washer box, valves and drain line with new washer box, valves and drain line. <b>Install new Washer Box</b>	<i>Div.# 11.A</i>	1 Ea	<input type="text"/>
<b>72</b>	<i>Area: KITCHEN</i> Water Heater/Gas/40 Gallon/Replace. Replace existing gas water heater with new 40 gal. gas water heater. Work shall include elevating to 18" (if in garage), replacement of TPR, all combustion air and gas & electrical hook-ups for code legal installation. <b>Install new HWT</b>	<i>Div.# 11.A</i>	1 Ea	<input type="text"/>
<b>Roofing</b>				
<b>73</b>	<i>Area: EXTERIOR</i> Roofing/Architectural/30 Year Warranty. Install architectural shingles/Minimum 30 year warranty//Use Owens Corning "Classic" or written approved equal. <b>Remove and Replace all drip edge, felt, fisdhing, shingles, and roof jacks</b>	<i>Div.# 7.A.</i>	26 Sq	<input type="text"/>
<b>Sheetmetal &amp; Gutters</b>				

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
<b>Sheetmetal &amp; Gutters</b>				
<b>74</b>	<i>Area: EXTERIOR</i> Vent/Install/T urbine. Install new turbine vent. <i>Install new roof vents</i>	Div.# 5.J	4 Ea	<input type="text"/>
<b>Site Work</b>				
<b>75</b>	<i>Area: EXTERIOR</i> Cleanup/Final. Final cleanup of entire Project. <i>Remove and trash, nails, and debris. Mow &amp; Weedeat yard.</i>	Div.#	1 SF	<input type="text"/>
<b>76</b>	<i>Area: INTERIOR</i> Cleanup/Final. Final cleanup of entire Project. <i>Remove all trash and debris</i>	Div.#	1 SF	<input type="text"/>
<p>All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.</p>				
<b>Total:</b>				<input type="text"/>