

HACN HOUSING REHAB SITE DIRECTIONS

Name: <u>Jennifer Murrell</u> Telephone: <u>(918)331-4281</u>

Address:

2316 N Wheeling Ave

Tulsa, OK 74110

County: Tulsa

Year Built:

GPS Coordinates: 36.18761 95.96492 Drive Time:



Directions: From Cherokee Nation, Turn left onto the US-412 W/Cherokee Turnpike W ramp Toll road 0.3 mi Continue on US-412 W to Tulsa. Take the Apache St exit from US-75 S43 min (47.0 mi) Merge onto US-412 W/Cherokee Turnpik Toll road 32.6 mi Keep left to stay on US-412 W 0.3 mi Continue onto I44/US-412 W 4.6 mi Use the right 2 lanes to turn slightly right onto I-244 W/US-412 W (signs for Sand Springs/Enid) 3.3 mi Take exit 12B for OK-11 W toward Tulsa International Airport 0.6 mi Continue onto OK-11 W 4.7 mi Continue onto Gilcrease Expy (signs for Downtown Tulsa/US-75 S/Okmulgee) 0.1 mi Use the left 2 lanes to merge onto US-75 S toward Downtown Tulsa/Okmulgee 0.6 mi Take the Apache St exit toward Lewis Ave 0.3 mi Continue on E Apache St/East 26th St N. Take N Xanthus Ave to N Wheeling Ave2 min (0.8 mi) Turn right onto E Apache St/East 26th St N0.4 mi Turn left onto N Xanthus Ave 0.2 mi Turn right onto E Young St364 ft Turn left at the 1st cross street onto N Wheeling Ave Destination will be on the right 174 ft2316 N Wheeling AveTulsa, OK 74110

DAV	GIPSON	018 883	5850
KAY	GIPSON	918-883-	· DOOU

Cost Estimator/Inspector

4/2/2024

Date

WorkWrite-Up and Bid Document/By Trade

Jennifer Murrell	Contractor Name:	2:		
2316 N Wheeling Ave Tulsa, OK	7-4110 Contractor Signature:	e:		
(918) 331-4281			This document must be signed to be a valid bid.	bid.
	PROJECT TYPE: Rehabilitation	ation	Bid Due Date:	
Trade Work Descr	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Carpentry				
Area: ROOF		Div.#6.C.	300 SF	
Exterior Wall/Repair. Replace exterior wall Sheathing 1/2" OSB (framing only).	wall Sheathing 1/2" OSB (framing	ng only).		
2 Area: EXTERIOR		Div.#6.P	150 LF	
⁼ ascia/Replace/1" x 6". Replace Fascia/ Use SmartSide Textured pre-primed Fascia material. Fastnen using recommended nails. Caulk and paint.	a/ Use SmartSide Textured pre-p I nails. Caulk and paint.	rimed Fascia		
3 Area: ROOF		Div.#6	900 LF	
Rafter Joists/Replace/2" x 8". Replace existing Rafter joists with new/ 2" x 8"	existing Rafter joists with new/ 2'	" × 8".		
RUN THE RAFTERS FROM THE PEAK OF HOUSE ALL WAY TO THE FLAT ROOF TO OUT A PITCH OVER THE FLAT ROOF JUST ON BACK OF HOUSE	K OF HOUSE ALL WAY TO THE	E FLAT ROOF TO		
Area: EXTERIOR		Div.#15	600 SF	
Siding/Lap Siding/Replace existing siding with new smart board siding (textured), primed.	ing with new smart board siding (textured), primed.		
Area: EXTERIOR		Div.#6.P	150 SF	
Soffit/Plywood/Install. Install new soffit with new SMART SIDE PRODUCT soffit material.	with new SMART SIDE PRODUC	CT soffit material.		
Paint & Finish				

Trade Work Description / Comments Gen. Spec. Q.	Qty Unit Item Bid
Paint & Finish	
6 Area: EXTERIOR Div.#9.N.4 50	500 SF
House/Paint/Two Coats. Paint exterior of the house (two coats). Include cleaning, caulking and filling of small holes. JUST WHAT THEY AND NOT THE HOLE HOUSE	
Plumbing	
7 Area: ROOF Div.#11.A	5Ea
Vent Pipe. Install new plumbing vent pipe. Extend new plumbing vent pipe through roof to code approved height.	_
Roofing Div #7 A	1
Roofing/Heritage/30 Year Warranty. Install fiberglass shingles/Minimum 30 year	
Drip Edge, Pipe Flashing, Valley Flashing, & Attic vents.	
9 Area: ROOF Div.#7.A 1144 SF	SF
Sheathing/7/16" OSB/Replace. Replace existing sheathing/Use 7/16" OSB.	
All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.	Total: