CHEROKEE NATION Environmental Programs



Asbestos Sampling Report

PARTICIPANT: DUNCAN, LILLIE

PREPARED BY: Logan Guty DATE: 11/1/2024

LOGAN GIRTY. ENVIRONMENTAL SPECIALIST III

REQUESTED BY: HACN HOUSING REHABILITATION (HUD) -

GEORGE HUBBARD

TABLE OF CONTENTS

- I. SITE INSPECTION/DESCRIPTION
- II. BACKGROUND
- III. FIELD PROCEDURES AND ANALYTICAL METHODS
- IV. SUMMARY OF FINDINGS
- V. CONCLUSIONS

APPENDIX A: PROJECT SCOPE OF WORK

APPENDIX B: LABORATORY REPORT & CHAIN OF CUSTODY

I. Site Inspection/Description

Cherokee Nation Environmental Programs (CNEP) has conducted asbestos sampling for the presence of asbestos containing materials (ACM) for the following site:

Lillie Duncan 1633 Linda Lane, Stilwell, OK 74960 918-507-3232 Coordinates: 35.8390 / -94.6354

The sampling was performed to determine the presence of all ACM from within the affected parts of the structure for EPA's National Emissions of Hazardous Air Pollutants (NESHAP) compliance as well as OSHA worker protection.

The inspector responsible for this project was:

Logan Girty, AHERA Inspector

The sampling was conducted on October 22, 2024 at the request of the Cherokee Nation Housing Rehabilitation Department.

The site is a single family home built in 1980. Sampling was limited to areas that would be affected by the project scope of work (Appendix A) provided by the housing rehabilitation department.

ACM was found at this site. See Section IV for locations.

II. BACKGROUND

The Oklahoma Department of Environmental Quality (ODEQ) has adopted EPA's NESHAP regulation under OAC252:100, 41-15 and has been delegated authority in the state of Oklahoma for its enforcement. Section 61.145(a) of Federal EPA regulation states that prior to commencement of the demolition or renovation of a facility a thorough inspection of the affected part or parts of a facility is required to determine the presence of all asbestos including Category I and Category II non-friable, and friable ACM. ACM is defined by EPA and OSHA as any material that contains greater than 1% asbestos.

III. FIELD PROCEDURES AND ANALYTICAL METHODS

During the on-site inspection, we visually assessed the physical characteristics of suspect asbestos-containing materials (SACM) based on homogeneous areas. Homogeneous areas are areas of asbestos similar in color, texture, and construction, date of application, and in general

appearance. For purposes of renovation and demolition, homogeneous areas of SACM can be further classified according to NESHAPs rules by whether the material is friable, Category I non-friable, or Category II non-friable.

<u>Friable ACM</u> is defined by NESHAPs rules as any material containing more than 1% asbestos as determined by Polarized Light Microscopy (PLM), that, when dry, can be crumbled, pulverized or reduced to powder by hand pressure.

<u>Category I Non-friable ACM</u> is defined by NESHAPs rules as any asbestos-containing packings, gaskets, construction mastics, resilient floor covering (i.e. floor tiles, roll sheet flooring) or asphalt roofing products that contain more than 1% asbestos as determined by PLM.

<u>Category II Non-friable ACM</u> is defined by NESHAPs rules as any material, excluding Category I non-friable ACM, containing more than 1% asbestos as determined by PLM, when dry, cannot be crumbled, pulverized, or reduced to powder by hand pressure.

Typically, non-friable materials, such as transite (cementious products) and vinyl floor tiles are not regulated by the State of Oklahoma provided they do not become friable. General deterioration, machine grinding, drilling, sanding, and dry-buffing are all ways of causing non-friable materials to become classified as Regulated Asbestos Containing Materials (RACM). All friable materials are classified RACM. Please note that the following materials, even though classified as non-friable are fully regulated by Oklahoma Department of Labor for removal purposes as friable material: ceiling tiles, roll sheet flooring (linoleum), and joint wall compound when deemed friable

In addition to classification of suspect material into friable and non-friable materials, a determination of current condition was conducted as part of the physical assessment. The condition noted is the representative of the material at the time of inspection. Conditions of materials can change very quickly when disturbed. All suspect material was placed in one of the following categories of condition.

<u>Significantly damaged</u>: Material that is damaged, blistered, deteriorated, water stained over at least 10% of its total area.

<u>Damaged</u>: Material that is damaged, blistered, deteriorated, water stained less than 10% of its total area.

Good: Material that has no visible damage or deterioration.

Guidelines used for the number of samples collected per homogeneous area were determined using the Asbestos Hazard Emergency Response Act (AHERA) protocol promulgated in 40 CFR 763, Appendix E as follows:

Surfacing materials – material that is sprayed or troweled on wall, ceilings, or support columns for fireproofing, acoustical, or even decorative purpose.

- Less than 1000 ft2 Minimum 3 samples
- From 1000-5000 ft2 Minimum 5 samples
- Greater than 5000 ft2 Minimum 7 samples

Thermal System Insulation (TSI) materials – thermal system insulation material applied to tanks, boiler, pipes or other structural component for an insulating purpose.

- May omit areas of fibrous glass, foam glass, rubber, and Styrofoam form sampling. Areas that have mastic on seams or outer jacketing will be sampled.
- At least three samples must be collected from each homogeneous area of TSI.
- Plus an additional sample from each patched area of less than 6 linear feet.
- Fittings require a sufficient amount to determine positive or negative nature.
- Inspector will first collect samples from damaged areas, exposed ends, or areas missing jacketing first.

Miscellaneous materials – all other material that are not thermal system insulation or surfacing materials. This includes gaskets, packings, joint wall compound, cementious asbestos materials, ceiling tiles resilient flooring materials, construction mastics, etc..

- May assume and document as such
- A sufficient amount of samples to determine negative or positive nature. A minimum or one per suspect homogeneous area.
- Collect samples from inconspicuous locations.
- Material such as cementious asbestos or vibration dampening cloths should not be sampled and will be assumed ACM unless instructed by client to collect these samples.

Bulk samples of suspect ACM were analyzed by Polarized Light Microscopy (PLM) in accordance with EPA Methods 600R-93/116. All samples were sent to a NVLAP accredited laboratory for analysis. QuanTEM Laboratories, LLC (NVLAP # 101959-0) in Oklahoma City, OK analyzed the samples. A copy of the full laboratory report and chain of custody can be found in Appendix B.

IV. SUMMARY OF FINDINGS

A total of 9 samples were analyzed from 3 homogeneous areas due to multi-layers of material within some homogeneous sample areas. All accessible and observable areas within the renovation area were sampled for ACM. Samples were not taken of suspect materials that may have placed the inspector at risk of injury (i.e. electrical panel boxes). Any suspect ACM that have not been tested and/or found positive for asbestos must be assumed ACM until they are analyzed. Upon review of laboratory analysis, the following asbestos containing materials can be found in Table 1. All suspect ACM samples that were analyzed and did not contain asbestos can be found in Table 2.

Asbestos Containing Materials				
Material Description	Locations	Friability (Friable, NF Cat I NF Cat II)	Condition	Sample Results (% Asbestos)
Vinyl Composition Tile (Black Mastic)	Throughout	NF Cat I	Signif. Damaged	4% Chrysotile
	Material Description Vinyl Composition Tile	Material Description Locations Vinyl Composition Tile Throughout	Material Description Locations Friability (Friable, NF Cat I NF Cat II) Vinyl Composition Tile Throughout NE Cat I	Material Description Locations Friability (Friable, NF Cat I NF Cat II) Vinyl Composition Tile Throughout NF Cat I Signif.

Table 2.	Non – Asbestos Containing Ma	terials		
Sample #	Material Description	Locations	Condition	Sample Results (% Asbestos)
01-01 01-02 01-03 01-04 01-05	Drywall Ceiling Texture	Throughout	Damaged	None Detected
03-01 03-02 03-03	Drywall Texture	Hall & Bath 2	Damaged	None Detected

V. CONCLUSIONS

Asbestos is not always an immediate hazard. Intact and undisturbed ACM does not pose a health risk. They may, however become a health hazard if they are damaged, disturbed, or deteriorate over time and release fibers into the air. There are no federal, state, or Tribal laws mandating asbestos removal. It is only when the material can no longer be maintained in good condition and/or airborne concentrations of asbestos are measured and found to be above a permissible exposure limit (PEL), or when the building is to be demolished or renovated, that removal may become necessary. Any renovation/demolition work which may impact these positive materials should be conducted in accordance with all applicable Federal, state, and local regulations.



2033 HERITAGE PARK DR, OKLAHOMA CITY, OK 73120 1.800.822.1650

Polarized Light Microscopy Asbestos Analysis Report

QuanTEM Lab No. 373749

Account Number:

C162

Date Received:

10/28/2024

Received By:

Baylie Longstreth

Date Analyzed:

10/30/2024

Analyzed By: Methodology:

Benjamin Hill EPA/600/R-93/116

Client: Cherokee Nation Environmental Programs

Logan Girty

PO Box 948

Tahlequah, OK 74464

Project: Lillie Duncan

Project Location: Stilwell

Project Number: N/A

QuanTEM Sample ID	Client Sample ID	Composition	Color / Description	Asbestos (%)	Non-Asbestos Fiber (%)	Non Fibrous
001	01-01	Homogeneous	White Ceiling Texture	Asbestos Not Present	NA	CaCO3 Foam Paint
002	01-02	Homogeneous	White Ceiling Texture	Asbestos Not Present	NA	CaCO3 Foam Paint
003	01-03	Homogeneous	White Ceiling Texture	Asbestos Not Present	NA	CaCO3 Foam Paint
004	01-04	Homogeneous	White Ceiling Texture	Asbestos Not Present	NA	CaCO3 Foam Paint
005	01-05	Homogeneous	White Ceiling Texture	Asbestos Not Present	NA	CaCO3 Foam Paint
006	02-01	Layered	White Floor Tile	Asbestos Not Present	NA	CaCO3 Vinyl

Unless otherwise noted, upon receipt the condition of the sample was acceptable for analysis.

QuanTEM is a NVLAP accredited Testing PLM laboratory (Lab Code: 101959-0). This report relates only to the specific items tested. NVLAP accreditation applies only to analysis performed utilizing EPA—40 CFR Appendix E to Subpart E of Part 763 and EPA/600/R-93/116 methods. This report may not be used to claim product endorsement by NVLAP or any agency of the US Government. This report may not be reproduced except in full, without the written approval of the laboratory.



2033 HERITAGE PARK DR, OKLAHOMA CITY, OK 73120 1.800.822.1650

Polarized Light Microscopy Asbestos Analysis Report

QuanTEM Lab No. 373749

Account Number: C162

Date Received:

10/28/2024

Received By:

Baylie Longstreth

Date Analyzed:

10/30/2024

Analyzed By: Methodology:

009

009a

03-03

Layered

Layered

Benjamin Hill EPA/600/R-93/116

Client: Cherokee Nation Environmental Programs

NA

Cellulose

Logan Girty

PO Box 948

Tahlequah, OK 74464

Project: Lillie Duncan

Project Location: Stilwell

Project Number:

N/A

QuanTEM Client Color / Non-Asbestos Non Fibrous Sample ID Sample ID Composition Description Asbestos (%) Fiber (%) 006a Layered Black Asbestos Present NA Tar Glue Chrysotile 4 Mastic 007 03-01 Layered White Asbestos Not Present NA CaCO3 Paint Texture 007a Layered White Asbestos Not Present Cellulose Gypsum Drywall 008 03-02 Layered White Asbestos Not Present NA CaCO3 Paint Texture 008a Layered White Asbestos Not Present Cellulose 10 Gypsum Drywall

Unless otherwise noted, upon receipt the condition of the sample was acceptable for analysis.

Asbestos Not Present

Asbestos Not Present

White

Texture

White

Drywall

QuanTEM is a NVLAP accredited Testing PLM laboratory (Lab Code: 101959-0). This report relates only to the specific items tested. NVLAP accreditation applies only to analysis performed utilizing EPA—40 CFR Appendix E to Subpart E of Part 763 and EPA/600/R-93/116 methods. This report may not be used to claim product endorsement by NVLAP or any agency of the US Government. This report may not be reproduced except in full, without the written approval of the laboratory.

CaCO3 Paint

Gypsum



2033 HERITAGE PARK DR, OKLAHOMA CITY, OK 73120

1.800.822.1650

Polarized Light Microscopy Asbestos Analysis Report

QuanTEM Lab No. 373749

Account Number:

C162

Date Received:

10/28/2024

Received By:

Baylie Longstreth

Date Analyzed:

10/30/2024

Analyzed By: Methodology: Benjamin Hill

EPA/600/R-93/116

Client: Cherokee Nation Environmental Programs

Logan Girty

PO Box 948

Tahlequah, OK 74464

Project: Lillie Duncan

Project Location: Stilwell

Project Number: N/A

Non-Asbestos

Non Fibrous

QuanTEM Sample ID Client

Sample ID

Composition

Color / Description

Asbestos (%)

Fiber (%)

Benjamin Hill

Benjamin Hill, Assistant Laboratory Manager

10/30/2024

Date of Report



ASBESTOS CHAIN OF CUSTODY

2033 Heritage Park Drive, Oklahoma City, OK 73120-7502 (800) 822-1650 • (405) 755-7272 • Fax: (405) 755-2058

Lab No. 373749

Page 1 of 1

Reject

Accept

LEGAL DOCUMENT - PLEASE PRINT LEGIBLY

										•	Canaly Company
		Conta	Contact Information				And the second	Proje	Project Information		Report Results (Solie Box)
Company:	y: Cherokee Nation Environmental Programs	Invironn	nental Programs	Phone: (91	(918) 453-6140		Project Name:	Lillie Duncan	can		QuanTEM Website
Contact:	Logan Girty			cell Phone: (918) 772-8346	8) 772		Project Location: Stilwell	Stilwell			Email logan-girty@cherokee.org
Account #:	1			E-mail: logan-gir	rty@cher	logan-girty@cherokee.org	Project ID:				Other
SAMPL	SAMPLED BY: Name: Logan Girty	Sirty		Date: 10/22	10/22/2024		P.O. Number:	896007			
	RELINQUISHED BY	HED BY		DATE & TIME	ME	>	VIA		RECEIVED BY	D BY	DATE & TIME
1	M & Coal			10/22/2024	24	F	FedEx	E	1		10/28/24 9-25
	1			5 PM							
					SERVI	CES (Plea	ESTED SERVICES (Please ☑ the Appropriate Boxes)	propriate	Boxes)		
	PIM		PLM			TEM			TEM		TURNAROUND TIME
<u>_</u>	Bulk Analysis (EPA 600/R-93/116)	16)	Vermiculite Attic Insulation	ulation	Air-	Air- AHERA		Bull	Bulk- Presence / Absence EPA600/R-93/116	:PA600/R-93/116	Rush
1	400 Point Count		(EPA 600/R-04/004)		Air-	Air-NIOSH 7402		Bull	Bulk-Quantitative [weight%]- Chatfield	%]- Chatfield	Same Day
	1000 Point Count		Omer		Air-	Air- ISO 10312			Dust- Presence / Absence		24 - Hour
	Gravimetric Preparation		PCM		Drir	Drinking Water- EPA 100.2	EPA 100.2		Dust- Quantitative [fibers/sq.cm]- ASTM D5755	sq.cm]- ASTM D5755	3 - Day
	Particle ID		NIOSH 7400		Was	ste Water- EPA	Waste Water- EPA 600/4-83-043	Other	ıer		5 - Day
No.	Sample ID (10 Characters Max) A	▼ To Be Analyzed ▼ To B	Color			Description	tion		Volume / Area (as applicable)	Сомм	Comments / Notes
-	01-01	$\overline{\Sigma}$	White		Dryw	all Ceiline	Drywall Ceiling Texture			Thr	Throughout
7	01-02	>	White		Dryw	all Ceilin	Drywall Ceiling Texture			Thr	Throughout
8	01-03	>	White		Dryw	all Ceilin	Drywall Ceiling Texture			Thr	Throughout
4	01-04	>	White		Dryw	all Ceilin	Drywall Ceiling Texture			Thr	Throughout
2	01-05	>	White		Dryw	all Ceilin	Drywall Ceiling Texture			Thr	Throughout
9	02-01	$\overline{\Sigma}$	White		Viny	Compos	Vinyl Composition Tile			Thr	Throughout
7	03-01	>	White		۵	Drywall Texture	exture			Hall	Hall & Bath 2

SATURDAY FEDEX SAMPLE DELIVERY - CALL TO SCHEDULE • Use this address for Saturday Delivery only: 4220 N. Santa Fe Ave., Oklahoma City, OK 73105-8517 • Mark Package "Hold for Saturday Pickup" Please Note - UPS and USPS are NOT available for Saturday Delivery

Hall & Bath 2 Hall & Bath 2

Drywall Texture Drywall Texture

White White

 \overline{D}

03-02

8 6 5