



Imagery ©2024 Airbus, Maxar Technologies, Map data ©2024 1000 ft

Tahlequah  
Oklahoma 74464

- ↑ 1. Head south on US-62 BUS W/S Muskogee Ave toward W Shawnee St  
 Pass by BancFirst (on the right in 0.2 mi) 1.8 mi
- ↪ 2. Turn right onto OK-51 W/OK-51BYP 0.5 mi
- ↶ 3. Turn left at the 1st cross street onto Stick Ross Mountain Rd 1.1 mi
- ↪ 4. Turn right onto W Stickcross Cir/W Stick Ross Mountain Cir 472 ft

W Stick Ross Mountain Cir  
Oklahoma 74464



Housing Authority of the Cherokee Nation  
 PO Box 1007,  
 Tahlequah, Oklahoma 74465-1007  
 918-456-5482 | 1-800-837-2869

Description	Quantity	Per
<b>ESTIMATE: Emergency (Housing Authority of the Cherokee Nation)</b>		<b>Claim #11703, Jason Whitmire</b>
Approved		
<b>ROOFPLAN: Roofplan</b>		
<b>Roof, Roof 2</b>  <b>Roof area:</b> 1,894.88 SF <b>Squares:</b> 18.9 SQ <b>Soffit:</b> 350.79 SF <b>Eaves:</b> 94.91 LF <b>Ridge:</b> 68.54 LF		
1 Shingles, Composition, Laminated/Architectural, Very Good - Replace	18.94 (20.83)	SQ
Includes 10% waste on material quantity.		
<b>SHINGLES</b>		
2 Shingles, Composition, 3-Tab, 25 Year - Tear Out	18.94	SQ
3 Shingles, Starter Row, Continuous - Replace	94.91 (104.40)	LF
Includes 10% waste on material quantity.		
4 Ridge Cap Shingles, 3-Tab - Replace	68.54 (75.39)	LF
Includes 10% waste on material quantity.		
<b>UNDERLAYMENTS</b>		
5 Sheathing, Material Only 1/2" OSB	1,894.88 (1,989.63)	SF
Includes 5% waste on material quantity.		
where needed		
6 Felt, Single Layer, 15 lb. - Replace	18.94	SQ
<b>VENTS AND FLASHINGS</b>		
7 Drip Edge, Eave/Rake, Galvanized - Tear Out	184.81	LF
8 Drip Edge, Eave/Rake, Galvanized - Replace	184.81 (194.05)	LF
Includes 5% waste on material quantity.		
9 Valley Flashing, Galvanized Steel - Tear Out	31.62	LF
10 Valley Flashing, Galvanized Steel - Replace	31.62 (33.20)	LF
Includes 5% waste on material quantity.		
11 Flashing, Pipe Jack, Aluminum - Tear Out	6	EA
12 Flashing, Pipe Jack, Aluminum - Replace	6	EA
<b>GUTTERS / DOWNSPOUTS / FASCIA</b>		
13 Fascia, Cedar, 1"x6" - Tear Out	184.81	LF
14 Fascia, Cedar, 1"x6" - Replace	184.81 (194.05)	LF
Includes 5% waste on material quantity.		
15 Fascia, 6" and Over - Prime & Paint	184.81	LF
<b>DEBRIS REMOVAL</b>		
16 No debris removal is needed for this estimate. The quantity is small enough that it can be discarded with local trash pick up.		
17 Dumpster 20 Yard	1	EA



Housing Authority of the Cherokee Nation  
PO Box 1007,  
Tahlequah, Oklahoma 74465-1007  
918-456-5482 | 1-800-837-2869

ESTIMATE: Emergency (Housing Authority of the Cherokee Nation)

Claim #11703, Jason Whitmire



Total: \_\_\_\_\_

Date: \_\_\_\_\_

Contractor  
Signature: \_\_\_\_\_