

HACN HOUSING REHAB SITE DIRECTIONS

Name: Kent ^{Fields} Fields
Telephone: (918) 489-5244

Address: PO Box 484 99163 Hwy 100
Gore, OK 74435

County: sequoyah **Year Built:** 1985

GPS Coordinates: 35.8535846,-94.9897532 **Drive Time:** 32 min



Directions: From Cherokee Nation, head north on S Cotton Wood St towards S Muskogee Ave 20ft .turn right onto US-62/S Muskogee Ave 0.6 mi.At the traffic circle,take the 1st exit onto State Hwy 82 4.7 mi.Turn right onto S Indian Rd15.2 mi.Turn left onto OK-10A S2.1 mi. Continue onto OK-100 E 2.5 mi house will be on the leftwith a big sign that says Natchez Nation

Eric Cheater
Cost Estimator/Inspector

3/14/24
Date



Housing Authority of the Cherokee Nation
 PO Box 1007,
 Tahlequah, Oklahoma 74465-1007
 918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Structure (Housing Authority of the Cherokee Nation)	Claim #11226, Kent Fields	

ROOFPLAN: Roofplan

Roof, Roof 3


Roof area: 2,428.51 SF Squares: 24.3 SQ Soffit: 460.89 SF
 Eaves: 138.46 LF Ridge: 67.63 LF



1 Shingles, Laminated/Architectural Elite - Replace <input type="checkbox"/> Includes 10% waste on material quantity.	24.29 (25.72)	SQ
2 Drip Edge (Rake + Eave) Galvanized - Replace <input type="checkbox"/> Includes 5% waste on material quantity.	247.26 (259.62)	LF
3 Shingles, Starter Row, Continuous - Replace <input type="checkbox"/> Includes 10% waste on material quantity.	138.46 (152.31)	LF
4 Ridge Cap Shingles, 3-Tab - Replace <input type="checkbox"/> Includes 10% waste on material quantity.	67.63 (74.39)	LF
5 Felt, Single Layer, 30 lb. - Replace	24.29	SQ
6 Vent Pipe Flashing, Furnace, Galvanized Steel, 4" - Tear Out	1	EA
7 Vent Pipe Flashing, Furnace, Galvanized Steel, 4" - Replace	1	EA
8 Fascia, Hardwood, 1"x6" - Tear Out <input type="checkbox"/> add one- by to fascia to match existing and remove bird boxing on the corner	247.26	LF
9 Fascia, Hardwood, 1"x6" - Replace <input type="checkbox"/> Includes 5% waste on material quantity.	247.26 (259.62)	LF
10 Soffit, Plywood, 3/8" - Tear Out	460.89	SF
11 Soffit, Plywood, 3/8" - Replace <input type="checkbox"/> Includes 5% waste on material quantity.	460.89 (483.94)	SF
12 Trucking & Hauling, 1/2 Ton	1	LD
13 ITEL, Shingles, 3-Tab, Tear Out	24.29	SQ
14 Step Flashing, Galvanized - Tear Out	31.19	LF
15 Step Flashing, Galvanized - Replace <input type="checkbox"/> Includes 5% waste on material quantity.	31.19 (32.75)	LF

Roof 2

Roof area: 373.29 SF Squares: 3.7 SQ Soffit: 139.52 SF
 Eaves: 30.00 LF Ridge: 15.00 LF



16 Shingles, Laminated/Architectural Elite - Replace <input type="checkbox"/> Includes 10% waste on material quantity.	3.73 (4.10)	SQ
17 Drip Edge (Rake + Eave) Galvanized - Replace <input type="checkbox"/> Includes 5% waste on material quantity.	79.76 (83.75)	LF



Housing Authority of the Cherokee Nation
PO Box 1007,
Tahlequah, Oklahoma 74465-1007
918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Structure (Housing Authority of the Cherokee Nation) Claim #11226, Kent Fields		
18. Shingles, Starter Row, Continuous - Replace <input type="checkbox"/> Includes 10% waste on material quantity.	30.00 (33.00)	LF
19. Ridge Cap Shingles, 3-Tab - Replace <input type="checkbox"/> Includes 10% waste on material quantity.	15.00 (16.50)	LF
20. Felt, Single Layer, 30 lb. - Replace	3.73	SQ
21. Fascia, Hardwood, 1"x6" - Tear Out	79.76	LF
22. Fascia, Hardwood, 1"x6" - Replace <input type="checkbox"/> Includes 5% waste on material quantity.	79.76 (83.75)	LF
23. Soffit, Plywood, 3/8" - Tear Out	139.52	SF
24. Soffit, Plywood, 3/8" - Replace <input type="checkbox"/> Includes 5% waste on material quantity.	139.52 (146.50)	SF
25. ITEL, Shingles, 3-Tab, Tear Out	3.73	SQ
26. Step Flashing, Galvanized - Remove	11.55	LF
27. Step Flashing, Galvanized - Tear Out	13.33	LF
28. Step Flashing, Galvanized - Replace <input type="checkbox"/> Includes 5% waste on material quantity.	13.33 (14.00)	LF