

Q & A 06.13.2024

- Is Type A agg base assumed to be present under the existing pavement, or should we include the removal and replacement of agg base in our bid item? **Assume to be present.**
- Is all asphalt on this project light duty? (4 inch) **All asphalt being replaced is light duty. Bidder to advise if a site layout of heavy duty and light duty asphalt is required.**
- Can we do the asphalt patching 30 days before the official start of the project, since it would not be too intrusive, and would allow the 30 day cure time before sealcoat/stripping? **Acceptable.**
- In Section 4-a-i of the Striping statement of work, it specifies that striping over sealcoat shall be placed no sooner than 20 hours, and no later than 24 hours. Am I to understand this as a 4 hour window for striping each phase? **Striping shall begin within the 20-24 hour window. Completion of each phase will vary based on amount of striping. It is anticipated no phase will require more than 10 hours to complete.**
- What is the expected application rate for sealcoat? **Reference manufacturer's installation guidelines.**
- What is the anticipated schedule, and are there liquidated damages? 60 days. **No liquidated damages. Owner reserves the right to assume the work if contractor is deemed to be deficient in completing the project.**