



5014 S Muskogee Ave
Tahlequah, OK 74464

- ↑ 1. Head east
404 ft
- ↶ 2. Turn left toward US-62 E/S Muskogee Ave
118 ft
- ↶ 3. Turn left onto US-62 E/S Muskogee Ave
1.8 mi
- ↷ 4. Turn right onto US-62 E
2.2 mi
- ↷ 5. Turn right to stay on US-62 E
7.7 mi
- ↑ 6. Continue straight onto Proctor Hill
0.7 mi
- ↷ 7. Turn right
0.1 mi

i Destination will be on the left

25957 US-62
Tahlequah, OK 74464



Housing Authority of the Cherokee Nation
 PO Box 1007,
 Tahlequah, Oklahoma 74465-1007
 918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Structure (Housing Authority of the Cherokee Nation)	Claim #10203, Wannie Ingram	
Approved		
FLOORPLAN: Floorplan		

handicap shower

1 Shower Stall, Fiberglass Very Good - Remove	1	EA	<hr/>
2 Shower Stall, Fiberglass Very Good - Replace	1	EA	<hr/>
<input type="checkbox"/> shower must have fold down seat, contractor must add backing between studs to anchor seat and grab bars			<hr/>
<input type="checkbox"/> shower must be handicap			<hr/>
3 Faucet & Showerhead Single Valve, Good - Remove	1	EA	<hr/>
4 Faucet & Showerhead Single Valve, Good - Replace	1	EA	<hr/>
<input type="checkbox"/> must use handheld shower head with stainless steel hose			<hr/>
5 Grab Bar, Handicap, per LF - Replace	2.00	LF	<hr/>
6 Toilet, Handicap Very Good - Remove	1	EA	<hr/>
7 Toilet, Handicap Very Good - Replace	1	EA	<hr/>
<input type="checkbox"/> must reuse braided waterline			<hr/>
8 Door, Interior, Pre-Hung Lauan, HC, Flush - Remove	2	EA	<hr/>
9 Door, Interior, Pre-Hung Lauan, HC, Flush - Replace	2	EA	<hr/>
<input type="checkbox"/> doors must be widened to 36"			<hr/>
10 Cabinet, Sink Base, Two Door 36"Wx34 1/2"Hx24"D, Economy - Remove	1	EA	<hr/>
11 Cabinet, Sink Base, Two Door 36"Wx34 1/2"Hx24"D, Economy - Replace	1	EA	<hr/>
12 Sink, Vitreous China Very Good - Tear Out	1	EA	<hr/>
13 Sink, Vitreous China Very Good - Replace	1	EA	<hr/>
14 Faucet, Bath Good - Replace	1	EA	<hr/>
15 Supply Line, Toilet, Flexible - Rem/Reset	1	EA	<hr/>
16 Supply Line, Sink, Flexible - Replace	2	EA	<hr/>
17 Medicine Cabinet Excellent - Remove	1	EA	<hr/>
18 Medicine Cabinet Excellent - Replace	1	EA	<hr/>
<input type="checkbox"/> cabinet must have mirror			<hr/>
19 Drywall, Up to 2' From Floor, 1/2" Taped - Replace	1.00 (1.06)	LF	<hr/>
<input type="checkbox"/> Includes 6% waste on material quantity.			<hr/>
<input type="checkbox"/> patch work to be done in closet in bathroom			<hr/>
20 Vinyl Sheet Flooring, .065" Very Good - Tear Out	80.00	SF	<hr/>
21 Vinyl Sheet Flooring, .065" Very Good - Replace	80.00 (88.00)	SF	<hr/>
<input type="checkbox"/> Includes 10% waste on material quantity.			<hr/>
<input type="checkbox"/> match to existing floor covering close as possible			<hr/>

Total:

date:

Signature:
