

**CHEROKEE NATION**  
**Environmental Programs**



**Asbestos Sampling Report**

**PARTICIPANT:** HARDIN, JOANNA

**PREPARED BY:** *Logan Girty* **DATE:** 8/16/2024  
LOGAN GIRTY, ENVIRONMENTAL SPECIALIST III

**REQUESTED BY:** HACN HOUSING REHABILITATION (HUD) –  
GEORGE HUBBARD

## TABLE OF CONTENTS

- I. SITE INSPECTION/DESCRIPTION
- II. BACKGROUND
- III. FIELD PROCEDURES AND ANALYTICAL METHODS
- IV. SUMMARY OF FINDINGS
- V. CONCLUSIONS

APPENDIX A: PROJECT SCOPE OF WORK

APPENDIX B: LABORATORY REPORT & CHAIN OF CUSTODY

## I. Site Inspection/Description

---

Cherokee Nation Environmental Programs (CNEP) has conducted asbestos sampling for the presence of asbestos containing materials (ACM) for the following site:

Joanna Hardin  
802 Barbara Dr, Muldrow, OK 74948  
918-427-4964  
Coordinates: 35.4012 / -94.6121

The sampling was performed to determine the presence of all ACM from within the affected parts of the structure for EPA's National Emissions of Hazardous Air Pollutants (NESHAP) compliance as well as OSHA worker protection.

The inspector responsible for this project was:

Logan Girty, AHERA Inspector

The sampling was conducted on August 6, 2024 at the request of the Cherokee Nation Housing Rehabilitation Department.

The site is a single family home built in 1978. Sampling was limited to areas that would be affected by the project scope of work (Appendix A) provided by the housing rehabilitation department.

**ACM was not found at this site.** See Section IV for locations.

## II. BACKGROUND

---

The Oklahoma Department of Environmental Quality (ODEQ) has adopted EPA's NESHAP regulation under OAC252:100, 41-15 and has been delegated authority in the state of Oklahoma for its enforcement. Section 61.145(a) of Federal EPA regulation states that prior to commencement of the demolition or renovation of a facility a thorough inspection of the affected part or parts of a facility is required to determine the presence of all asbestos including Category I and Category II non-friable, and friable ACM. ACM is defined by EPA and OSHA as any material that contains greater than 1% asbestos.

## III. FIELD PROCEDURES AND ANALYTICAL METHODS

---

During the on-site inspection, we visually assessed the physical characteristics of suspect asbestos-containing materials (SACM) based on homogeneous areas. Homogeneous areas are areas of asbestos similar in color, texture, and construction, date of application, and in general

appearance. For purposes of renovation and demolition, homogeneous areas of SACM can be further classified according to NESHAPs rules by whether the material is friable, Category I non-friable, or Category II non-friable.

Friable ACM is defined by NESHAPs rules as any material containing more than 1% asbestos as determined by Polarized Light Microscopy (PLM), that, when dry, can be crumbled, pulverized or reduced to powder by hand pressure.

Category I Non-friable ACM is defined by NESHAPs rules as any asbestos-containing packings, gaskets, construction mastics, resilient floor covering (i.e. floor tiles, roll sheet flooring) or asphalt roofing products that contain more than 1% asbestos as determined by PLM.

Category II Non-friable ACM is defined by NESHAPs rules as any material, excluding Category I non-friable ACM, containing more than 1% asbestos as determined by PLM, when dry, cannot be crumbled, pulverized, or reduced to powder by hand pressure.

Typically, non-friable materials, such as transite (cementitious products) and vinyl floor tiles are not regulated by the State of Oklahoma provided they do not become friable. General deterioration, machine grinding, drilling, sanding, and dry-buffing are all ways of causing non-friable materials to become classified as Regulated Asbestos Containing Materials (RACM). All friable materials are classified RACM. Please note that the following materials, even though classified as non-friable are fully regulated by Oklahoma Department of Labor for removal purposes as friable material: ceiling tiles, roll sheet flooring (linoleum), and joint wall compound when deemed friable

In addition to classification of suspect material into friable and non-friable materials, a determination of current condition was conducted as part of the physical assessment. The condition noted is the representative of the material at the time of inspection. Conditions of materials can change very quickly when disturbed. All suspect material was placed in one of the following categories of condition.

Significantly damaged: Material that is damaged, blistered, deteriorated, water stained over at least 10% of its total area.

Damaged: Material that is damaged, blistered, deteriorated, water stained less than 10% of its total area.

Good: Material that has no visible damage or deterioration.

Guidelines used for the number of samples collected per homogeneous area were determined using the Asbestos Hazard Emergency Response Act (AHERA) protocol promulgated in 40 CFR 763, Appendix E as follows:

Surfacing materials – material that is sprayed or troweled on wall, ceilings, or support columns for fireproofing, acoustical, or even decorative purpose.

- Less than 1000 ft<sup>2</sup> – Minimum 3 samples
- From 1000-5000 ft<sup>2</sup> – Minimum 5 samples
- Greater than 5000 ft<sup>2</sup> – Minimum 7 samples

Thermal System Insulation (TSI) materials – thermal system insulation material applied to tanks, boiler, pipes or other structural component for an insulating purpose.

- May omit areas of fibrous glass, foam glass, rubber, and Styrofoam from sampling. Areas that have mastic on seams or outer jacketing will be sampled.
- At least three samples must be collected from each homogeneous area of TSI.
- Plus an additional sample from each patched area of less than 6 linear feet.
- Fittings require a sufficient amount to determine positive or negative nature.
- Inspector will first collect samples from damaged areas, exposed ends, or areas missing jacketing first.

Miscellaneous materials – all other material that are not thermal system insulation or surfacing materials. This includes gaskets, packings, joint wall compound, cementitious asbestos materials, ceiling tiles resilient flooring materials, construction mastics, etc..

- May assume and document as such
- A sufficient amount of samples to determine negative or positive nature. A minimum of one per suspect homogeneous area.
- Collect samples from inconspicuous locations.
- Material such as cementitious asbestos or vibration dampening cloths should not be sampled and will be assumed ACM unless instructed by client to collect these samples.

Bulk samples of suspect ACM were analyzed by Polarized Light Microscopy (PLM) in accordance with EPA Methods 600R-93/116. All samples were sent to a NVLAP accredited laboratory for analysis. QuanTEM Laboratories, LLC (NVLAP # 101959-0) in Oklahoma City, OK analyzed the samples. A copy of the full laboratory report and chain of custody can be found in Appendix B.

#### IV. SUMMARY OF FINDINGS

---

A total of 11 samples were analyzed from 5 homogeneous areas due to multi-layers of material within some homogeneous sample areas. All accessible and observable areas within the renovation area were sampled for ACM. Samples were not taken of suspect materials that may have placed the inspector at risk of injury (i.e. electrical panel boxes). Any suspect ACM that have not been tested and/or found positive for asbestos must be assumed ACM until they are analyzed. Upon review of laboratory analysis, the following asbestos containing materials can be found in Table 1. All suspect ACM samples that were analyzed and did not contain asbestos can be found in Table 2.

<b>Table 1. Asbestos Containing Materials</b>					
Sample #	Material Description	Locations	Friability (Friable, NF Cat I NF Cat II)	Condition	Sample Results (% Asbestos)

<b>Table 2. Non – Asbestos Containing Materials</b>				
Sample #	Material Description	Locations	Condition	Sample Results (% Asbestos)
01-01	Shingle	Roof	Damaged	None Detected
02-01 Thru 02-03	Drywall Ceiling Texture	HVAC Closet	Damaged	None Detected
03-01	Wall Tile	Bath/Kitchen	Damaged	None Detected
04-01	Floor Tile	Bath/Entry	Damaged	None Detected
05-01 Thru 05-05	Drywall Texture	Throughout	Damaged	None Detected

## V. CONCLUSIONS

Asbestos is not always an immediate hazard. Intact and undisturbed ACM does not pose a health risk. They may, however become a health hazard if they are damaged, disturbed, or deteriorate over time and release fibers into the air. There are no federal, state, or Tribal laws mandating asbestos removal. It is only when the material can no longer be maintained in good condition and/or airborne concentrations of asbestos are measured and found to be above a permissible exposure limit (PEL), or when the building is to be demolished or renovated, that removal may become necessary. Any renovation/demolition work which may impact these positive materials should be conducted in accordance with all applicable Federal, state, and local regulations.



2033 HERITAGE PARK DR, OKLAHOMA CITY, OK 73120 | 1.800.822.1650

### Polarized Light Microscopy Asbestos Analysis Report

QuanTEM Lab No. 371597	Client: Cherokee Nation Environmental Programs
Account Number: C162	Logan Girty
Date Received: 08/13/2024	PO Box 948
Received By: Baylie Longstreth	Tahlequah, OK 74464
Date Analyzed: 08/15/2024	Project: Joanna Hardin
Analyzed By: Tanner Smith	Project Location: Muldrow
Methodology: EPA/600/R-93/116	Project Number: N/A

QuanTEM Sample ID	Client Sample ID	Composition	Color / Description	Asbestos (%)	Non-Asbestos Fiber (%)	Non Fibrous
001	01-01	Layered	Black/Brown Shingle	Asbestos Not Present	Cellulose 2 Glass Fiber 15	Tar CaCO3 Sand
001a		Layered	Black Tar	Asbestos Not Present	NA	Tar
002	02-01	Layered	Tan Ceiling Texture	Asbestos Not Present	NA	CaCO3 Mica Paint
002a		Layered	White Drywall	Asbestos Not Present	Cellulose 10	Gypsum
003	02-02	Homogeneous	Tan Ceiling Texture	Asbestos Not Present	NA	CaCO3 Mica Paint
004	02-03	Layered	Tan Ceiling Texture	Asbestos Not Present	NA	CaCO3 Mica Paint

Unless otherwise noted, upon receipt the condition of the sample was acceptable for analysis.

QuanTEM is a NVLAP accredited Testing PLM laboratory (Lab Code: 101959-0). This report relates only to the specific items tested. NVLAP accreditation applies only to analysis performed utilizing EPA—40 CFR Appendix E to Subpart E of Part 763 and EPA/600/R-93/116 methods. This report may not be used to claim product endorsement by NVLAP or any agency of the US Government.

This report may not be reproduced except in full, without the written approval of the laboratory.



2033 HERITAGE PARK DR, OKLAHOMA CITY, OK 73120 | 1.800.822.1650

### Polarized Light Microscopy Asbestos Analysis Report

QuanTEM Lab No. 371597	Client: Cherokee Nation Environmental Programs
Account Number: C162	Logan Girty
Date Received: 08/13/2024	PO Box 948
Received By: Baylie Longstreth	Tahlequah, OK 74464
Date Analyzed: 08/15/2024	Project: Joanna Hardin
Analyzed By: Tanner Smith	Project Location: Muldrow
Methodology: EPA/600/R-93/116	Project Number: N/A

QuanTEM Sample ID	Client Sample ID	Composition	Color / Description	Asbestos (%)	Non-Asbestos Fiber (%)	Non Fibrous
004a		Layered	Off-white Drywall	Asbestos Not Present	Cellulose 10	Gypsum
005	03-01	Layered	White Wall Tile	Asbestos Not Present	NA	Clay Sand
005a		Layered	Cream Mastic	Asbestos Not Present	NA	Glue
006	04-01	Layered	White Floor Tile	Asbestos Not Present	NA	Clay Sand
006a		Layered	Gray Mortar	Asbestos Not Present	NA	CaCO3 Sand
007	05-01	Homogeneous	Tan Texture	Asbestos Not Present	NA	CaCO3 Paint
008	05-02	Layered	Tan Texture	Asbestos Not Present	NA	CaCO3 Paint

Unless otherwise noted, upon receipt the condition of the sample was acceptable for analysis.

Quantem is a NVLAP accredited Testing PLM laboratory (Lab Code: 101959-0). This report relates only to the specific items tested. NVLAP accreditation applies only to analysis performed utilizing EPA—40 CFR Appendix E to Subpart E of Part 763 and EPA/600/R-93/116 methods. This report may not be used to claim product endorsement by NVLAP or any agency of the US Government. This report may not be reproduced except in full, without the written approval of the laboratory.





2033 HERITAGE PARK DR, OKLAHOMA CITY, OK 73120 | 1.800.822.1650

### Polarized Light Microscopy Asbestos Analysis Report

QuanTEM Lab No. 371597	Client: Cherokee Nation Environmental Programs
Account Number: C162	Logan Girty
Date Received: 08/13/2024	PO Box 948
Received By: Baylie Longstreth	Tahlequah, OK 74464
Date Analyzed: 08/15/2024	Project: Joanna Hardin
Analyzed By: Tanner Smith	Project Location: Muldrow
Methodology: EPA/600/R-93/116	Project Number: N/A

QuanTEM Sample ID	Client Sample ID	Composition	Color / Description	Asbestos (%)	Non-Asbestos Fiber (%)	Non Fibrous
008a		Layered	White Drywall	Asbestos Not Present	Cellulose 10	Gypsum
009	05-03	Layered	Tan Texture	Asbestos Not Present	NA	CaCO3 Paint
009a		Layered	White Drywall	Asbestos Not Present	Cellulose 10	Gypsum
010	05-04	Homogeneous	White Joint Compound	Asbestos Not Present	NA	CaCO3
011	05-05	Layered	Tan Texture	Asbestos Not Present	NA	CaCO3 Gypsum Paint
011a		Layered	Yellow Mastic	Asbestos Not Present	NA	Glue

Unless otherwise noted, upon receipt the condition of the sample was acceptable for analysis.

Quantem is a NVLAP accredited Testing PLM laboratory (Lab Code: 101959-0). This report relates only to the specific items tested. NVLAP accreditation applies only to analysis performed utilizing EPA—40 CFR Appendix E to Subpart E of Part 763 and EPA/600/R-93/116 methods. This report may not be used to claim product endorsement by NVLAP or any agency of the US Government.

This report may not be reproduced except in full, without the written approval of the laboratory.



2033 HERITAGE PARK DR, OKLAHOMA CITY, OK 73120 | 1.800.822.1650

### Polarized Light Microscopy Asbestos Analysis Report

QuanTEM Lab No. 371597      Client: Cherokee Nation Environmental Programs  
Account Number: C162      Logan Girty  
Date Received: 08/13/2024      PO Box 948  
Received By: Baylie Longstreth      Tahlequah, OK 74464  
Date Analyzed: 08/15/2024      Project: Joanna Hardin  
Analyzed By: Tanner Smith      Project Location: Muldrow  
Methodology: EPA/600/R-93/116      Project Number: N/A

QuanTEM Sample ID	Client Sample ID	Composition	Color / Description	Asbestos (%)	Non-Asbestos Fiber (%)	Non Fibrous
-------------------	------------------	-------------	---------------------	--------------	------------------------	-------------

Tanner Smith, Laboratory Analyst

8/15/2024

Date of Report

Unless otherwise noted, upon receipt the condition of the sample was acceptable for analysis.

QuanTEM is a NVLAP accredited Testing PLM laboratory (Lab Code: 101959-0). This report relates only to the specific items tested. NVLAP accreditation applies only to analysis performed utilizing EPA—40 CFR Appendix E to Subpart E of Part 763 and EPA/600/R-93/116 methods. This report may not be used to claim product endorsement by NVLAP or any agency of the US Government.

This report may not be reproduced except in full, without the written approval of the laboratory.



# ASBESTOS CHAIN OF CUSTODY

2033 Heritage Park Drive, Oklahoma City, OK 73120-7502  
 (800) 822-1650 • (405) 755-7272 • Fax: (405) 755-2058

## LEGAL DOCUMENT - PLEASE PRINT LEGIBLY

For Lab Use Only  
 Lab No. 371597  
 Accept  Reject

Report Results  one box  
 QuanTEM Website  
 Email logan-girty@cherokee.org  
 Other \_\_\_\_\_

Project Information  
 Project Name: Joanna Hardin  
 Project Location: Muldrow  
 Project ID: \_\_\_\_\_  
 P.O. Number: 874586

Contact Information  
 Company: Cherokee Nation Environmental Programs  
 Phone: (918) 453-6140  
 Contact: Logan Girty  
 Cell Phone: (918) 772-8346  
 Account #: C 162  
 E-mail: logan-girty@cherokee.org  
 Name: Logan Girty  
 Date: 8/6/2024

RELINQUISHED BY: Joanna E. Girty DATE & TIME: 8/12/2024 12 pm  
 RECEIVED BY: [Signature] DATE & TIME: 8/13/24 9:10  
 VIA: FedEx

REQUESTED SERVICES (Please  the Appropriate Boxes)

PLM	PLM	PLM	TEM	TEM	TEM	TURNAROUND TIME
<input checked="" type="checkbox"/> Bulk Analysis (EPA 600/R-93/116)	<input type="checkbox"/> Vermiculite Attic Insulation (EPA 600/R-04/004)	<input type="checkbox"/> Air- AHERA	<input type="checkbox"/> Bulk- Presence / Absence EPA600/R-93/116	<input type="checkbox"/> Air- NIOSH 7402	<input type="checkbox"/> Bulk- Quantitative [weight%]- Chatfield	<input type="checkbox"/> Rush
<input type="checkbox"/> 400 Point Count	<input type="checkbox"/> Other	<input type="checkbox"/> Air- ISO 10312	<input type="checkbox"/> Dust- Presence / Absence	<input type="checkbox"/> Drinking Water- EPA 100.2	<input type="checkbox"/> Same Day	<input type="checkbox"/> Same Day
<input type="checkbox"/> 1000 Point Count	<input type="checkbox"/> PCM	<input type="checkbox"/> Waste Water- EPA 600/4-83-043	<input type="checkbox"/> Dust- Quantitative (fibers/sq.cm)- ASTM D5755	<input type="checkbox"/> Other	<input type="checkbox"/> 24 - Hour	<input type="checkbox"/> 24 - Hour
<input type="checkbox"/> Gravimetric Preparation	<input type="checkbox"/> NIOSH 7400				<input checked="" type="checkbox"/> 3 - Day	<input checked="" type="checkbox"/> 3 - Day
<input type="checkbox"/> Particle ID					<input type="checkbox"/> 5 - Day	<input type="checkbox"/> 5 - Day

No.	Sample ID (10 Characters Max)	To Be Analyzed	Color	Description	Volume / Area (as applicable)	Comments / Notes
1	01-01	<input checked="" type="checkbox"/>	Black/Brown	Shingle		Roof
2	02-01	<input checked="" type="checkbox"/>	Tan	Drywall Ceiling Texture		HVAC Closet
3	02-02	<input checked="" type="checkbox"/>	Tan	Drywall Ceiling Texture		HVAC Closet
4	02-03	<input checked="" type="checkbox"/>	Tan	Drywall Ceiling Texture		HVAC Closet
5	03-01	<input checked="" type="checkbox"/>	White	Wall Tile		Bath/Kitchen
6	04-01	<input checked="" type="checkbox"/>	White	Floor Tile		Bath/Entry Area
7	05-01	<input checked="" type="checkbox"/>	Tan	Drywall Texture		Throughout
8	05-02	<input checked="" type="checkbox"/>	Tan	Drywall Texture		Throughout
9	05-03	<input checked="" type="checkbox"/>	Tan	Drywall Texture		Throughout
10	05-04	<input checked="" type="checkbox"/>	Tan	Drywall Texture		Throughout

SATURDAY FEDEX SAMPLE DELIVERY - CALL TO SCHEDULE • Use this address for Saturday Delivery only: 4220 N. Santa Fe Ave., Oklahoma City, OK 73105-8517 • Mark Package "Hold for Saturday Pickup"  
 Please Note - UPS and USPS are NOT available for Saturday Delivery



# ASBESTOS CHAIN OF CUSTODY

2033 Heritage Park Drive, Oklahoma City, OK 73120-7502  
 (800) 822-1650 • (405) 755-7272 • Fax: (405) 755-2058

**LEGAL DOCUMENT - PLEASE PRINT LEGIBLY**

For Lab Use Only	
Lab No. <u>371597</u>	Accept <input checked="" type="radio"/> Reject <input type="radio"/>

Project Information		Project Name: Joanna Hardin	Project Location: Muldrow		
No.	Sample ID (10 Characters Max)	Color	Description	Volume / Area (as applicable)	Comments / Notes
11	05-05	Tan	Drywall Texture		Throughout
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					