

HACN HOUSING REHAB SITE DIRECTIONS

Name: <u>Courtney Reasons</u> Telephone: <u>1918</u>1530-6934

Address:

1999 SW 34 Rd

Locust Grove, OK 74352

County: Mayes

Year Built: 1987

GPS Coordinates: 36,15855 J-95,2770],

Drive Time: 45 min



Directions: From Cherokee Nation,
Take Hwy 82 north 29.2 mile to Hwy 412 [Locust Grave]
Take Hwy 412 west 6.4 mile to Murphy Rd
(2/10 mile east of Neosha river)
Turn left - south - on Murphy Rd go 2 mile
house on left - Daycare sign

David Tackott

Cost Estimator/Inspector

3-5-21

Date

WorkWrite-Up and Bid Document/By Trade

Courtney Reason (B.E.)	Contractor Name:		
1999 SW 34 Rd Locust Grove, OK 7-4352	Contractor Signature:		
(810) 330-0834	This document mu	This document must be signed to be a valid bid	bid.
PROJE	PROJECT TYPE: Emergency Repairs	Bid Due Date:	
Trade Work Description / Comments	nments Gen. Spec.	Qty Unit	Item Bid
Carpentry			
1 Area: BATHROOM #1	Div.#6.N	30 LF	
Base Trim/Pine, K- Pattern 2-1/4" Solid/ Stain Grade /Replace. Replace base trim, K-Trim, solid pine,2-1/4". Stain & Finish.	ade /Replace. Replace base trim, K-		
2 Area: BEDROOM #1	<i>Div.</i> #6.N	40 LF	
Base Trim/Pine, K- Pattern 2-1/4" Solid/ Stain Grade /Replace. Replace base trim, K-Trim, solid pine,2-1/4". Stain & Finish.	ade /Replace. Replace base trim, K-		
3 Area: BEDROOM #2	<i>Div.</i> #6.N	40 LF	
Base Trim/Pine, K- Pattern 2-1/4" Solid/ Stain Grade /Replace. Replace base trim, K-Trim, solid pine,2-1/4". Stain & Finish.	ade /Replace. Replace base trim, K-		
4 Area: HALLWAY #1	<i>Div.</i> #6.N	50 LF	
Base Trim/Pine, K- Pattern 2-1/4" Solid/ Stain Grade /Replace. Replace base trim, K-Trim, solid pine,2-1/4". Stain & Finish.	ade /Replace. Replace base trim, K-		
Flooring			

Trade Work Description / Comments Gen. Spec.	Qty Unit	Item Bid
Flooring		
5 Area: BATHROOM #1 Div.#9.L	56 SF	
Flooring/ Install vinyl/waterproof/flooring planks/base trim. Install vinyl planks with 20 mil wear layer, 5.0 mil backing with 25 year residential warranty. Work shall include floor level, seal concrete, moisture resistant glue and top seal.		
Get with homeowner on color Remove flooring.		
6 Area: BEDROOM #1 Div.#9.L	90 SF	
Flooring/ Install vinyl/waterproof/flooring planks/base trim. Install vinyl planks with 20 mil wear layer, 5.0 mil backing with 25 year residential warranty. Work shall include floor level, seal concrete, moisture resistant glue and top seal.		
Get with homeowner on color Remove carpet		
7 Area: BEDROOM #2	90 SF	
Flooring/ Install vinyl/waterproof/flooring planks/base trim. Install vinyl planks with 20 mil wear layer, 5.0 mil backing with 25 year residential warranty. Work shall include floor level, seal concrete, moisture resistant glue and top seal.		
Get with homeowner on color Remove carpet	84 SE	
Flooring/ Install vinyl/waterproof/flooring planks/base trim. Install vinyl planks with 20 mil wear layer, 5.0 mil backing with 25 year residential warranty. Work shall include floor level seal concrete moisture resistant glue and ton seal		
Get with homeowner on color		

compliance with the more stringent requirement.