



Imagery ©2025 TerraMetrics, Map data ©2025 Google 2 mi

Tahlequah
Oklahoma 74464

- ↑ 1. Head south on S Muskogee Ave toward W Shawnee St
 i Pass by BancFirst (on the right in 0.2 mi) 4.1 mi
- ↻ 2. At the traffic circle, take the 2nd exit onto State Hwy 82 9.6 mi
- ↶ 3. Turn left onto OK-100 E 2.5 mi
- ↷ 4. Turn right onto S 585 Rd 2.5 mi
- ↷ 5. Turn right onto S 584 Rd 1.0 mi
- ↷ 6. Turn right onto E 888 Rd/N4590 Rd 0.6 mi

25712 E 888 Rd
Bunch, OK 74931




Housing Authority of the Cherokee Nation
 PO Box 1007,
 Tahlequah, Oklahoma 74465-1007
 918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Emergency (Housing Authority of the Cherokee Nation)	Claim #10043, Sharon Hayes	
Approved		

FLOORPLAN: Floorplan

Bathroom


Length: 12' Width: 8' Height: 8' Flat
 Walls: 368.00 SF Walls-subs: 351.33 SF Walls-subs-cas-bsbd: 257.44 SF
 Doors: 16.67 SF Windows: 0.00 SF Openings: 0.00 SF Missing Walls: 0.00 SF
 Floor: 95.00 SF Ceiling: 95.00 SF Perim (F): 42.92 LF Perim (C): 46.00 LF



1 /SHOWER WITH GRAB BARS AND A GLIDE BAR.		
2 HANDICAP ADA APPROVED	1	EA
3 Plumbing Fixtures, Remove & Bag Tub & Shower Unit	1	EA
4 Showerhead Elite - Replace	1	EA
This is an ADA APPROVED WALL MOUNTED GLIDE BAR WITH SEPARATE REMOVABLE SHOWER HEAD WITH HOSE.		
5 Replace ADA SCALD VALVE APPROVED SINGLE HANDLE	1	EA
6 Grab Bar Straight, 24"L, 1" DIA. - Replace	2	EA
BACKING IS TO BE ADDED BEHIND SHOWER FOR ALL GRAB BAR INSTALLATIONS		
7 Grab Bar, Handicap, per LF - Replace	3.00	LF
36" GRAB BAR FOR SHOWER WITH BACKING ADDED BEFORE INSTALLATION.		
8 Grab Bar L-Shape, 1" Dia. - Replace	1	EA
FLOOR/WALL MOUNTED GRAB BAR FOR STOOL AREA.		
9 Toilet, Handicap Excellent - Replace	1	EA
10 Replace - Bathroom Sink, Excellent Includes drain assembly	1	EA
11 Plumbing Fixtures, Remove & Bag Bathroom Sink	1	EA
12 Faucet, Sink, Single Valve, Very Good - Replace	1	EA
13 Toggle & Tub Drain Assembly - Replace	1	EA
14 Valve, Water Shutoff Angle 1/2" - Replace	3	EA
15 Drywall, Wall/Ceiling, Remove & Bag	224.00	SF
16 Drywall, Walls 1/2 Green Board &		
17 Drywall, Ceiling 1/2", Green Board - Replace	224.00 (235.20)	SF
Includes 5% waste on material quantity.		
18 Drywall/Plaster Ceiling - Prime & Paint	95.00	SF
19 Drywall/Plaster Wall - Prime & Paint	257.44	SF
20 Texture, Walls, Splatter/Orange Peel - Replace	257.44	SF
21 Base Molding, Stain Grade, Up to 3" - Replace	18.25 (19.35)	LF
Includes 6% waste on material quantity.		
22 Casing - Stain & Finish	57.00	LF
23 Exhaust Fan Good - Replace	1	EA
24 Countertop, Imitation Marble - Replace	4.00	LF
25 Towel Bar Good - Replace	1	EA
26 Dispenser, Toilet Tissue Excellent - Replace	1	EA
27 Towel Ring, Excellent - Replace	1	EA
28 Cabinet, Full Height, Economy - Replace	2.00	LF
29 Replace -Mirrored Medicine Cabinet Excellent W/ Light	1	EA



Housing Authority of the Cherokee Nation
PO Box 1007,
Tahlequah, Oklahoma 74465-1007
918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Emergency (Housing Authority of the Cherokee Nation)  Approved	Claim #10043, Sharon Hayes	
Bathroom(con't)		
30 Ceiling Fixture Very Good - Replace	1	EA

Total : _____

Date : _____

Contractor: _____

Signature: _____