

HOUSING REHAB SITE DIRECTIONS

Name: J.D. Webster

Telephone: (918)708-4686

Address: 20351 Steely Hollow Rd
Tahlequah, OK 74464

GPS Coordinates: 35.9787, -94.93874

Drive Time: 30 min

Directions: From Cherokee Nation, Take Hwy 82 north, from stoplight in front of Wal-Mart take Hwy 82 north 6.5 miles turn right on Steely Hollow Rd. Go 2 miles turn right before you get to Red Community building, house is behind Community building

C. Gann
Inspector

11/21/2024
Date

WorkWrite-Up and Bid Document/By Trade

J D Webster (HAF Roof) Contractor Name:

20351 Steely Hollow Rd Tahlequah, OK 7- Contractor Signature:

(918) 708-4686 *This document must be signed to be a valid bid.*

PROJECT TYPE: Rehabilitation Bid Due Date:

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Roofing				
1	Area: ROOF Roofing/Heritage/30 Year Warranty. Install fiberglass shingles/Minimum 30 year warranty/Use Marlkey/Tamko or written approved equal. 30 lb Felt, Painted Style D Drip Edge, Pipe Flashing, Valley Flashing, Step Flashing & Attic vents.	Div.# 7.A.	20 Sq	<input style="width: 50px; height: 30px;" type="text"/>
2	Area: ROOF Roofing/Strip/Asphalt-Fiberglass1 Layers. Strip roof--asphalt/fiberglass/1 layers.	Div.# 7.C	17.5 Sq	<input style="width: 50px; height: 30px;" type="text"/>
3	Area: ROOF Sheathing/Replace/Match Existing. Replace existing sheathing. Match existing as closely as possible. Replace decking where needed.	Div.# 7.B	128 SF	<input style="width: 50px; height: 30px;" type="text"/>

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
	<p>All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.</p>			<p>Total: <input type="text"/></p>