

HOUSING REHAB SITE DIRECTIONS

Name: Calvin Sanders

Telephone: (918)798-7386

Address: 507 S. 13th St
Collinsville, OK 74021

GPS Coordinates: 36.35989,-95.84023

Drive Time: 1.5 hrs

Directions: From Cherokee Nation, Take Hwy 62 west to Muskogee, turn right on Muskogee Turnpike. Go to Tulsa take a right on Hwy 169 north to Collinsville. When coming into Collinsville take the exist Hwy west 20 (E 146 st). Turn left on Hwy 20 to Collinsville, go to S. 13 th st turn left, go 1/4 mile house is on the left.

C. Gann
Inspector

11/26/2024
Date

WorkWrite-Up and Bid Document/By Trade

Calvin Sanders (HAF Roof)
 507 S. 13th St Collinsville, OK 7-4021
 (918) 798-7386

Contractor Name:

Contractor Signature:

This document must be signed to be a valid bid.

PROJECT TYPE: Rehabilitation **Bid Due Date:**

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Carpentry				
1	Area: ROOF Fascia/Cover with Metal-Aluminum min .027 thick Heavy Duty Aluminum with baked on finish. Pop rivet all corners and joints. Rolled stiffener bead. Install on the south gable where the fascis is exposed.	Div.# 15.C.	14 LF	
Roofing				
2	Area: ROOF Roofing/Heritage/30 Year Warranty. Install fiberglass shingles/Minimum 30 year warranty/Use Marlarky/Tamko or written approved equal. 30 lb Felt, Painted Style D Drip Edge, Pipe Flashing, Valley Flashing, Step Flashing & Attic vents.	Div.# 7.A.	22 Sq	
3	Area: ROOF Roofing/Strip/Asphalt-Fiberglass 1 Layers. Strip roof--asphalt/fiberglass/1 layers. Remove the main house and garage only, do not remove the roll roofing.	Div.# 7.C	20 Sq	
4	Area: ROOF Sheathing/Replace/Match Existing. Replace existing sheathing. Match existing as closely as possible. Replace the decking where needed.	Div.# 7.B	96 SF	

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Sheetmetal & Gutters				
5	Area: ROOF Gutters & Downspouts/Remove and Reinstall. Remove existing gutter and downspouts.Reinstall existing gutters and downspouts using new hardware and fasteners. Clean and recaulk all connections..	Div.# 7.F.	90 LF	
Dont remove on the back side where the roof has the roll roofing				

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.

Total: