



HACN HOUSING REHAB SITE DIRECTIONS

Name: Linda Cooper

Telephone: (918)434-3573

Address: 1428 E 488 Rd
Salina, OK 74365

County: Delaware **Year Built:** 1985

GPS Coordinates: 36.311832-94.980488 **Drive Time:** 1hr

Directions: From Cherokee Nation, Turn left go 2mi turn right go 2mi towards 82/62 continue north on 82 for 3mi turn right onto hwy 82a continue to E650 rd turn right at liberty grace chapel continue to N556 rd turn left go north to 412, continue north approx 4.5mi to cr488 turn left second drive on right 1st house on left

Melvin Blossom
Cost Estimator/Inspector

1/28/2025
Date

WorkWrite-Up and Bid Document/By Trade

Linda Cooper

1428 E 488 Rd Salina, OK 7-4365

(918) 434-3573

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: Emergency Repairs **Bid Due Date:**

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Roofing				
1	Area: ROOF Roofing/Heritage/30 Year Warranty. Install fiberglass shingles/Minimum 30 year warranty/Use Marlarky/Tamko or written approved equal. 30 lb Felt, Painted Style D Drip Edge, Pipe Flashing, Valley Flashing, Step Flashing & Attic vents.	Div.# 7.A.	32 Sq	<input style="width: 50px; height: 30px;" type="text"/>
2	Area: ROOF Roofing/Strip/Asphalt-Fiberglass. Remove all layers, and haul roofing debris to a Legal Waste Dump for disposal.	Div.# 7.C	32 Sq	<input style="width: 50px; height: 30px;" type="text"/>
3	Area: ROOF Sheathing/7/16" OSB/Replace. Replace existing sheathing/Use 7/16" OSB Where needed.	Div.# 7.A	160 SF	<input style="width: 50px; height: 30px;" type="text"/>

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
-------	-----------------------------	------------	----------	----------

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement.

Total: