



Tahlequah
Oklahoma 74464

Take S Indian Rd and OK-100 E to S Railroad St/SE RR St
in Gore

46 min (32.8 mi)

Homeowner
phone # 918-235-1628
cell # 918-713-7701

- ↑ 1. Head south on S Muskogee Ave toward W Shawnee St
 i Pass by BancFirst (on the right in 0.2 mi)
4.0 mi
- ↶ 2. Keep left to continue on US-62 W
223 ft
- ↻ 3. At the traffic circle, take the 2nd exit onto State Hwy 82
4.8 mi
- ↷ 4. Turn right onto S Indian Rd
15.2 mi
- ↶ 5. Turn left onto OK-10A S
2.1 mi
- ↑ 6. Continue onto OK-100 E
6.6 mi

Follow S Railroad St/SE RR St and Ensminger St to Geneva Cir

- ↶ 7. Turn left onto S Railroad St/SE RR St
2 min (0.3 mi)
- ↷ 8. Turn right onto Ensminger St
0.1 mi
- ↑ 9. Continue onto Geneva Cir
 i Destination will be on the right
144 ft

112 Geneva Cir
Gore, OK 74435



Housing Authority of the Cherokee Nation
PO Box 1007,
Tahlequah, Oklahoma 74465-1007
918-456-5482 | 1-800-837-2869


Description	Quantity	Per
ESTIMATE: Emergency (Housing Authority of the Cherokee Nation)		Claim #11796, Lisa Brooks
FLOORPLAN: Floorplan		

Windows

1 Window, Single-Hung, Aluminum, Up to 10 SF - Remove	4	EA	_____
2 Vinyl Replacement Window, Double-Hung, 6-10 SF - Replace	4	EA	_____
Replace aluminum windows in the two front bedrooms, kitchen and converted garage.			
3 Trucking & Hauling, 1/2 Ton	1	LD	_____

Living Room


Length: 19'11" **Width:** 20'4" **Height:** 8' Flat
Walls: 644.00 SF **Walls-sub:** 644.00 SF **Walls-sub-cas-bsbd:** 620.53 SF
Doors: 0.00 SF **Windows:** 0.00 SF **Openings:** 0.00 SF **Missing Walls:** 0.00 SF
Floor: 329.97 SF **Ceiling:** 329.97 SF **Perim (F):** 80.50 LF **Perim (C):** 80.50 LF



4 Texture, Popcorn, Medium, Ceilings - Remove	329.97	SF	_____
5 Texture, Popcorn, Medium, Ceilings - Replace	329.97	SF	_____
6 Drywall Tape/Joint Repair	20.33	LF	_____
Repair seams and refasten where Sheetrock is sagging.			
7 Drywall/Plaster Ceiling - Prime & Paint	329.97	SF	_____

Bedroom

Length: 11'10" **Width:** 18'11" **Height:** 8' Flat
Walls: 492.00 SF **Walls-sub:** 492.00 SF **Walls-sub-cas-bsbd:** 474.08 SF
Doors: 0.00 SF **Windows:** 0.00 SF **Openings:** 0.00 SF **Missing Walls:** 0.00 SF
Floor: 223.85 SF **Ceiling:** 223.85 SF **Perim (F):** 61.50 LF **Perim (C):** 61.50 LF



8 Texture, Popcorn, Medium, Ceilings - Remove	223.85	SF	_____
9 Texture, Popcorn, Medium, Ceilings - Replace	223.85	SF	_____
10 Drywall Tape/Joint Repair	61.50	LF	_____
Repair seams and refasten where Sheetrock is sagging.			
11 Drywall/Plaster Ceiling - Prime & Paint	223.85	SF	_____

Bathroom

Length: 7'7" **Width:** 4'11" **Height:** 8' Flat
Walls: 200.00 SF **Walls-sub:** 182.23 SF **Walls-sub-cas-bsbd:** 171.03 SF
Doors: 17.78 SF **Windows:** 0.00 SF **Openings:** 0.00 SF **Missing Walls:** 0.00 SF
Floor: 37.28 SF **Ceiling:** 37.28 SF **Perim (F):** 21.75 LF **Perim (C):** 25.00 LF



12 Drywall Tape/Joint Repair	21.75	LF	_____
13 Drywall/Plaster Ceiling - Prime & Paint	37.28	SF	_____
14 Toilet, 2 Piece, Good - Remove	1	EA	_____



Housing Authority of the Cherokee Nation
PO Box 1007,
Tahlequah, Oklahoma 74465-1007
918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Emergency (Housing Authority of the Cherokee Nation)		Claim #11796, Lisa Brooks
Approved		

Bathroom(con't)

15 Toilet, Handicap Excellent - Replace	1	EA	_____
16 Plumbing Fixtures, Remove & Bag Bathtub Surround, Fiberglass	1	EA	_____
17 Plumbing Fixtures, Remove & Bag Bathtub, Fiberglass	1	EA	_____
18 Shower Stall, Fiberglass Good - Replace	1	EA	_____
Install low curb handicap shower w/seat.			
19 Faucet & Showerhead Single Valve, Good - Remove	1	EA	_____
20 Faucet & Showerhead Single Valve, Good - Replace	1	EA	_____
21 Showerhead Good - Remove	1	EA	_____
22 Showerhead Good - Replace	1	EA	_____
Install hand held shower faucet with rail.			
23 Grab Bar, Handicap, per LF - Replace	8.00	LF	_____
Install four 2' grab bars.			
24 Sink, Pedestal, Vitreous China Good - Replace	1	EA	_____
25 Plumbing Fixtures, Remove & Bag Bathroom Sink	1	EA	_____
26 Faucet, Bath Good - Remove	1	EA	_____
27 Faucet, Bath Good - Replace	1	EA	_____
28 Supply Line, Toilet, Flexible - Remove	1	EA	_____
29 Supply Line, Toilet, Flexible - Replace	1	EA	_____
30 Supply Line, Sink, Flexible - Remove	2	EA	_____
31 Supply Line, Sink, Flexible - Replace	2	EA	_____
32 Drywall/Plaster Wall - Prime & Paint	171.03	SF	_____
33 Vinyl Plank Flooring, Good - Replace	37.28 (41.01)	SF	_____
Includes 10% waste on material quantity.			
34 Remove & Bag, Tile Floor	37.28	SF	_____
35 Base Molding, Paint Grade, Over 3" - Up to 6" - Remove	21.75	LF	_____
36 Base Molding, Paint Grade, Over 3" - Up to 6" - Replace	21.75 (23.06)	LF	_____
Includes 6% waste on material quantity.			
Installation should include paint or finish.			
37 Interior Door, Pre-hung, Lauan, HC, Flush - Remove	1	EA	_____
38 Interior Door, Pre-hung, Lauan, HC, Flush - Replace	1	EA	_____
Widen rough opening to accept widest door possible.			
Installation should include paint or finish.			
39 Lockset, Interior, Privacy, Good - Remove	1	EA	_____
40 Lockset, Interior, Privacy, Good - Replace	1	EA	_____

Total: \$ _____

Date: _____

Contractor
Signature: _____