

## HACN HOUSING REHAB SITE DIRECTIONS

Name: <u>Toni Weetona Ruark</u> Telephone: <u>(918)315-3167</u>

Address:

705 S Main

Sallisaw, OK 74955

County: Sequoyah

Year Built: 1940

GPS Coordinates: <u>35.45281</u>, <u>-94.79578</u> Drive Time: <u>45 min</u>



**Directions:** From Cherokee Nation, Head South on 82 in to Cookson, make a left on S Blue Top rd toward Marble City straight to Sallisaw. Right at the light on W Cherokee Ave then left on N Washington St, at the end tur right across train tracks then left on W Port Arthur Pl at the end right on S Main house will be on the right after Payne St.

Kaleb Kingfisher

11/18/2024

Cost Estimator/Inspector

Date

## WorkWrite-Up and Bid Document/By Trade

| Toni Weetona Ruark  | Contractor Name:   |   |             |
|---|--|---|-------------|
| 705 S Main Sallisaw, OK   | 7-4955   |   |             |
| (918) 315-3167  | Contractor Signature:  |   |             |
|   | This document  | This document must be signed to be a valid bid. | id.         |
|   | PROJECT TYPE: Emergency Repairs  | Bid Due Date:                                   |             |
| Trade We  | Work Description / Comments Gen. Spec.   | Qty Unit  | Item Bid    |
| Carpentry   |  |   |             |
| 1 Area: EXTERIOR  | Div.#6.M.2   | 80 LF   |             |
| Level /Floor: Place Double 2"   | Level /Floor: Place Double 2"x 8" girder beams beneath floor joist, concrete block piers   |   |             |
| Level Entire Home   |  |   |             |
| 2 Area: INTERIOR  | Div.#6.N   | 450 LF  |             |
| Base Trim/Pine, K- Pattern 2-1/4" Sol Trim, solid pine,2-1/4". Stain & Finish.  | Base Trim/Pine, K- Pattern 2-1/4" Solid/ Stain Grade /Replace. Replace base trim, K-Trim, solid pine,2-1/4". Stain & Finish.   |   |             |
| 3 Area: INTERIOR  | <i>Div.</i> #6.D   | 1300 SF   |             |
| Subfloor/Repair/3/4" T/G Plywood. Repair subfloor 3/4" written approved equal as vapor barrier beneath subfloor.  | Subfloor/Repair/3/4" T/G Plywood. Repair subfloor 3/4" T/G plywood. Use Tyvek or written approved equal as vapor barrier beneath subfloor.   |   |             |
| Flooring  |  |   |             |
| 4 Area: INTERIOR  | <i>Div.</i> #9.L   | 1300 SF   |             |
| Flooring/ Install vinyl/waterproof/flooring planks/base trin wear layer, 5.0 mil backing with 25 year residential warra level, seal concrete, moisture resistant glue and top seal. | Flooring/ Install vinyl/waterproof/flooring planks/base trim. Install vinyl planks with 20 mil wear layer, 5.0 mil backing with 25 year residential warranty. Work shall include floor level, seal concrete, moisture resistant glue and top seal. |   |             |
|   |  |   |             |
| Print Date: Monday, November 18, 2024   | 705 S Main Sallisaw, OK 7-4955   |   | Page I of 2 |

compliance with the more stringent requirement.